

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-093-10002-00-01
Spot: NENE Sec/Twnshp/Rge: 33-25S-36W
4620 feet from S Section Line, 660 feet from E Section Line
Lease Name: LEE A Well #: A1-SWD
County: KEARNY Total Vertical Depth: 5070 feet

KAC
BEM
5-12-05
CP-4
fee

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: PO BOX 8647
WICHITA, KS 67208

CIBP Size: feet: 1800
CIBP Size: feet: 2255 WITH 2 SX CMT
COND Size: 13.38 feet: 560
PROD Size: 5.5 feet: 5070 WITH 125 SX CMT
SURF Size: 8.625 feet: 2250

\$16478

Well Type: SWD UIC Docket No: D10069.0 Date/Time to Plug: 03/28/2005 8:00 AM

Plug Co. License No.: 33346 Plug Co. Name: TR SERVICE AND RENTAL, INC.

Proposal Rcvd. from: TERRY RICHARDSON Company: TR SERVICE AND RENTAL, INC. Phone: (620) 672-9100

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING REPORT.

Plugging Proposal Received By: STEVE DURRANT

WitnessType: NONE

Date/Time Plugging Completed: 03/31/2005 5:00 PM

KCC Agent: STEVE DURRANT

Actual Plugging Report:

Perfs:

PBTD 4022'. 2 3/8" PLASTIC LINED TUBING SET @ 2945' ON BAKER AD-1. TOP OF TUBING FISH @ 2260'. SET CIBP @ 2255' & 2 SX CMT. 1ST PLUG SET 8 5/8" CIBP @ 1800' & 25 SX CMT THROUGH TUBING. RAN CMT BOND LOG. TOC @ 550'. 2ND PLUG PULL 530' OF 8 5/8" CASING. RAN TUBING TO 530'. MIXED & PUMPED 60 SX CMT. 3RD PLUG PULL TUBING TO 90'. CIRCULATE CMT TO 0' WITH 40 SX CMT.

RECEIVED
MAY 12 2005
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2000' OF 5 1/2" CASING.

Plugged through: TBG

District: 01

MAY 10 2005

MD

Signed Steve Durrant (TECHNICIAN)

INVOICED
DATE 5-12-05
INV. NO. 2005061561