

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-20831-00-00
Spot: SWSE Sec/Twnshp/Rge: 22-32S-8W
660 feet from S Section Line, 1980 feet from E Section Line
Lease Name: FULTON Well #: 1
County: HARPER Total Vertical Depth: 3850 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N. MARKET, SUITE 1000
WICHITA, KS 67202

CIBP Size: feet: 3600
PROD Size: 4.5 feet: 3812 150 SX CMT
SURF Size: 8.625 feet: 272 200 SX CLASS A

#125¹³

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/28/2005 8:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: JOHN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: Perf 3636' - 3684'; CIBP 3600', Perf 3406' - 3424'; CIBP 2750' & 35 sxs; 1250 & 35 sxs; 800' & 35 sxs; circ 325' - 0'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: NONE
Date/Time Plugging Completed: 04/28/2005 5:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP was set at 3350' and capped with 3 sacks of cement. Recovered 2750' of 4-1/2" casing. Pulled casing to 1250' and spotted 35 sacks of cement. Pulled casing to 800' and spotted 35 sacks of cement. Pulled casing to 325' and circulated cement to surface.
Allied Cement #16403
60/40 posmix with 4% gel

Perfs:

Top	Bot	Thru	Comments
3678	3684		
3658	3670		
3636	3648		
3418	3424		
3406	3410		

RECEIVED
KCC DISTRICT #2
MAY 10 2005
WICHITA, KS

RECEIVED
MAY 13 2005
KCC WICHITA

Remarks:
Plugged through: CSG

District: 02

Signed [Signature]
(TECHNICIAN)

INVOICED
DATE 5-16-05
INV. NO. 2005061577