

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20539-00-00
Spot: NESESW Sec/Twnshp/Rge: 30-17S-10W
990 feet from S Section Line, 3300 feet from E Section Line
Lease Name: BECK Well #: 1
County: ELLSWORTH Total Vertical Depth: 3297 feet

Operator License No.: 7030
Op Name: EVANS, JOHN ROY
Address: BOX 385 405 FOURTH STREET
CLAFLIN, KS 67525

PROD Size: 5.5 feet: 3292 100 SX
SURF Size: 8.625 feet: 240 200 SX

#107¹⁵

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/21/2005 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: GREG EVES WitnessType: PARTIAL
Date/Time Plugging Completed: 04/21/2005 2:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 2940' and put 5 sacks of cement on top. Attempt to pull casing: parted at 500'. Perforated at 1250' and 950'. Ran tubing to 1250' and pumped 35 sacks of cement. Pulled tubing to 950' and pumped 35 sacks of cement. Pulled tubing to 290' and circulated cement to surface.

Copeland Cement #25439

60/40 posmix with 4% gel

Perfs:

Top	Bot	Thru	Comments
2990	2996		
RECEIVED KCC DISTRICT #2 APR 29 2005 WICHITA, KS			
RECEIVED MAY 13 2005 KCC WICHITA			

Remarks:

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

INVOICED
DATE 5-16-05
INV. NO. 2005061569