

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20578-00-00
Spot: SESESW Sec/Twnshp/Rge: 30-17S-10W
330 feet from S Section Line, 2970 feet from E Section Line
Lease Name: BECK Well #: 2
County: ELLSWORTH Total Vertical Depth: 2990 feet

Operator License No.: 7030
Op Name: EVANS, JOHN ROY
Address: BOX 385 405 FOURTH STREET
CLAFLIN, KS 67525

CIBP Size: feet: 3290
PROD Size: 5.5 feet: 3305 125 SX
SURF Size: 8.625 feet: 251 225 SX

\$97¹⁸

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/25/2005 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL
Date/Time Plugging Completed: 04/25/2005 12:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 2940' and put 5 sacks of cement on top of sand. Cut off casing at 2200'. Pulled casing to 1250' and pumped 35 sacks of cement. Pulled casing to 950' and pumped 35 sacks of cement. Pulled casing to 300' and circulated cement to surface.

Copeland Cement #25314
60/40 posmix with 4% gel

Perfs: **RECEIVED
KCC DISTRICT #2
APR 29 2005
WICHITA, KS**

**RECEIVED
MAY 13 2005
KCC WICHITA**

Remarks:
Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

INVOICED
DATE 5-16-05
INV. NO. 2005061569