

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21933-00-00
Spot: SWNWSW Sec/Twnshp/Rge: 35-30S-10W
1650 feet from S Section Line, 330 feet from W Section Line
Lease Name: HENNING Well #: 1
County: KINGMAN Total Vertical Depth: 4438 feet

Operator License No.: 31191
Op Name: R & B OIL & GAS, INC.
Address: 904 N. LOGAN PO BOX 195
ATTICA, KS 67009

SURF Size: 8.625 feet: 237 200 SX CMT 60/40 POZ, 3% CC, 3% GEL.

#144²⁴

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/01/2005 8:00 AM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: JOHN ARMBRUSTER Company: DUKE DRILLING CO., INC. Phone: (620) 254-7251

Proposed 35 sxs @ 1500'
Plugging 35 sxs @ 750'
Method: 35 sxs @ 290'
25 sxs @ 60'
15 sxs in rathole & 10 sxs in mousehole

Plugging Proposal Received By: STEVE VANGIESON WitnessType: NONE
Date/Time Plugging Completed: 01/01/2005 5:00 PM KCC Agent: STEVE VANGIESON

RECEIVED
KCC DISTRICT #2
MAY 10 2005
WICHITA, KS

Actual Plugging Report:

Ran open end drill pipe to 1500' and spotted 35 sacks of cement. Pulled drill pipe to 750' and spotted 35 sacks of cement. Pulled drill pipe to 290' and spotted 35 sacks of cement. Pulled drill pipe to 60' and circulated 25 sacks of cement. Circulated 15 sacks of cement in rathole and 10 sacks of cement in mousehole.

Allied Cement #17345
60/40 posmix with 4% gel

Perfs:

RECEIVED
MAY 13 2005
KCC WICHITA

Remarks:

Plugged through: DP

District: 02

Signed _____

(TECHNICIAN)

INVOICED

DATE 5-16-05

INV. NO. 2005061575