

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-155-21483-00-00  
Spot: N2SWSE Sec/Twnshp/Rge: 6-22S-10W  
990 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: BLACK TRUST Well #: 1  
County: RENO Total Vertical Depth: 3615 feet

Operator License No.: 6804  
Op Name: LACHENMAYR, HOWARD DBA LACHE  
Address: 904 EMMALINE  
NEWTON, KS 67114

SURF Size: 8.625 feet: 310

#117 49

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/02/2005 12:00 PM  
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.  
Proposal Rcvd. from: DARRYL Company: SOUTHWIND DRILLING, INC. Phone: (620) 564-3800

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DONALD HOBERECHT Witness Type: NONE  
Date/Time Plugging Completed: 05/02/2005 5:00 PM KCC Agent: DONALD HOBERECHT

Actual Plugging Report:

Spotted 35 sacks of cement at 2950'. Pulled out of hole at 1350' and spotted 35 sacks of cement. Pulled out of hole at 850' and spotted 35 sacks of cement. Pulled out of hole at 300' and spotted 35 sacks of cement. Pulled out of hole at 60' and circulated 25 sacks of cement to surface. Pumped 15 sacks of cement in rathole and 10 sacks of cement in mousehole.

Allied Cementing #18309  
60/40 posmix with 4% gel

Perfs:

RECEIVED  
KCC DISTRICT #2  
MAY 3 - 2005  
WICHITA, KS


RECEIVED  
MAY 13 2005  
KCC WICHITA

Remarks:

Plugged through: DP

District: 02

Signed



(TECHNICIAN)

INVOICED

DATE 5-16-05

INV. NO. 2005061572