

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market . Room 2078
Wichita, . Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM

15-009-15298-00-00 (PLEASE TYPE FORM and File ONE Copy)
API # Drld 1943 (Identifier number of this well).

WELL OPERATOR John J. Darrah, Jr. KCC LICENSE # 5088
ADDRESS 225 N. Market #300 CITY Wichita
STATE KS ZIP CODE 67202 CONTACT PHONE # (316) 263-2243
LEASE Hogan A | WELL #5 SEC 11 T 17 R 11 WEST
SPOT LOCATION NE NW NE COUNTY Barton

4950 FEET (in exact footage) from South North LINE OF SECTION

1650 FEET (in exact footage) from East West LINE OF SECTION

OILWELL GAS WELL D&A SWD/ENHR WELL DOCKET #

CONDUCTOR CASING SIZE none SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8 5/8 SET AT 245 CEMENTED WITH 150 SACKS

PRODUCTION CASING SIZE 5 1/2 SET AT 3374 CEMENTED WITH 75 SACKS

LIST (ALL) PERFORATIONS and BRIDGE PLUG SETS OPEN HOLE 3374-3393---4' Slick liner set at 3367 w/50 sx. calc t/Cement 2204'---- 5 1/2 Had been squeezed 460 and 2362 in 1971

Temp survey 2300'

ELEVATION 1949 KB GL TD 3393 PBTD ANHYDRITE DEPT

CONDITION OF WELL GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Pump 20 sx cement w/ sand and hulls to bottom. Part 4" at free point pull to 1200 (salt), pump 30 sk plug, Pull 4" to @ 250'. pump 30 sk plug. Plug in top.

RECEIVED
MAY 20 2005
KCC WICHITA

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS AGO-1 FILED?

If not explain why?) drilled 1943

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. sec. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

George Stoepelwerth PHONE 316-263-2243

ADDRESS above City/State

PLUGGING CONTRACTOR Copeland KCC LICENSE # 99981

ADDRESS P.O. Box 438 Haysville, KS 67060-0428 PHONE 316-524-1225

PROPOSED DATE AND HOUR OF PLUGGING (If known?)

PAYMENT OF THE PLUGGING FEE (K.A.S. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE May 16, 2005 OPERATOR/AUTHORIZED AGENT

KCC *[Signature]*
MAY 19 2005
HAYS, KS

WELL RECORD

Company Cities Service Oil Co. Well No. 5 Farm Hogan "A"
 Location 330' South and 990' East of N/4 Corner Sec. 11 T. 17 R. 11W
 Elevation 1949 County Barton State Kansas
 Drlg. Comm. April 30, 1943 Contractor Hisson Drilling Company
 Drlg. Comp. May 18, 1943 Acid None
 T. D. 3393' Initial Prod. Depthograph Potential: 1495 oil, no water, 24 hrs.

CASING RECORD:

8-5/8" 245' cem. 150 sz cement
 5-1/2" 3374' cem. 75 sz Ash Grove

FORMATION RECORD:

shale & shells	0-784
broken lime & shale	1030
shale & shells	1200
salt & shale	1310
shale & shells	1510
lime & shale	1700
shale & lime	1850
shale	1860
lime broken	1922
lime	1975
shale & shells	2075
lime & shale	2190
shale & shells	2335
shale & lime	2475
shale	2520
sand & lime	2535
lime	2538
shale & lime	2685
broken lime	2775
lime & shale	2838
lime	3377

3377 Rot. TD = 3378 SDM
 lime 3393 T. D.

Corr. Top Arbuckle 3372'
 Penetration 21'
 Total Depth 3393'

Fillup: 200' oil in 3/4 hr. @ 3379
 450' oil in 3 1/2 hrs. @ 3382
 985' oil in 6 1/2 hrs. @ 3387
 2950' oil in 10 hrs. @ 3393

5-20-43: Temporary physical potential,
 455 oil, no water, 24 hours.

Syfo: 500' 0°
 1000' 0°
 1500' 0°
 2000' 0°
 2400' 0°
 3000' 0°

RECEIVED
 MAY 20 2005
 KCC WICHITA

KCC
 MAY 19 2005
 HAYS, KS

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Darrah, John Jay, Jr.
225 North Market, Ste 300
Wichita, KS 67202-3408

May 20, 2005

Re: HOGAN A #5
API 15-009-15298-00-00
NENWNE 11-17S-11W, 4950 FSL 1650 FEL
BARTON COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #4
2301 E. 13th
Hays, KS 67601
(785) 625-0550

Sincerely


David P. Williams
Production Supervisor