

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22720-00-00
Spot: SWNWNW Sec/Twnshp/Rge: 7-7S-21W
4290 feet from S Section Line, 4950 feet from E Section Line
Lease Name: ANITA DAVIS Well #: 2
County: GRAHAM Total Vertical Depth: 1862 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: BOX 783188 8100 E 22ND ST. N. #700
WICHITA, KS 67278

PROD Size: 4.5 feet: 1862 485 SX CMT CIRCULATED TO SURFACE
SURF Size: 8.625 feet: 204 150 SX CMT *\$60⁵²*

Well Type: SWD UIC Docket No: D26842.0 Date/Time to Plug: 05/06/2005 9:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: PETER J. FIORINI Company: RITCHIE EXPLORATION, INC. Phone: (785) 623-1506

Proposed
Plugging
Method:

Plugging Proposal Received By: HERB DEINES
Date/Time Plugging Completed: 05/06/2005 11:00 AM

Witness Type: COMPLETE (100%)
KCC Agent: ROGER MOSES

Actual Plugging Report:

Tied to 4 1/2" casing - squeezed 125 sxs cement with 500# hulls.
Max. P.S.I. 500#. S.I.P. 250#.
Tied to 8 5/8" x 4 1/2" annulus - squeezed 5 sxs cement.
Max. P.S.I. 500#. S.I.P.0#.
Total of 130 sxs 60/40 pozmix - 10% gel and 500# hulls.

Perfs:

Top	Bot	Thru	Comments
1538	1577		

RECEIVED
MAY 20 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. KELLER TANK-WATER.

Plugged through: CSG

District: 04

Signed *Roger L. Moses*

(TECHNICIAN)

INVOICED

DATE 5-20-05

INV. NO. 2005061599

Form CP-2/3

MAY 18 2005

replacement card

RITCHIE EXPLORATION
WICHITA KS 67202

7-07S-21W
SW NW NW

#2 DAVIS, ANITA

site: 4-3/4 N & 5 W OF NICODEMUS KS ay: GRAHAM API 15-065-22720

contr: MURFIN DRILLING #8 field: ANITA

geol: K KESSLER

fr date 06/30/93 spd date 08/10/93 drlg comp 08/14/93 card issued 01/10/94 last revised 03/11/96

ELV: 2233 KB, 2228 GL LOG
 tops.....depth/ datum

PBTD1798 + 435
 ANH1853 + 380
 B/ANH1884 + 349
 TOP3232 -999
 HEEB3441 -1208
 TOR3463 -1230
 LANS3480 -1247
 BKC3669 -1436
 LTD3694 -1461
 RTD3696 -1463

IP status:
 SWDW, CED HILL 1538-1577, 10/06/93
 INFO RELEASED: 3/11/96 - WAS SWDW - TIGHT HOLE
 CSG: 8-5/8" 204 / 150 SX (ALT 2), 4-1/2" 1861.85 / 485 SX
 NO CORES OR DSTS
 TRGT ZN: LKC, ARB, PTD 3775 (ARB), MICT - CO, PF
 (CED HILL) 1538-1577, W / 1 SPF, SET 2-3/8" TBG & PKR
 AT 1493.72, COMP AS SWDW - INJECTION RATE
 SATISFACTORY, 10/6/93

COPYRIGHT 1996
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS