

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20907-00-00
Spot: SENENE Sec/Twnshp/Rge: 8-12S-15W
4290 feet from S Section Line, 330 feet from E Section Line
Lease Name: OSWALD-WILCOX A Well #: 30
County: RUSSELL Total Vertical Depth: 3263 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

PROD Size: 5.5 feet: 3253 w/300 sxs cmt
SURF Size: 8.625 feet: 1360 w/125 sxs cmt

\$ 106⁰⁵

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/17/2005 8:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORPORATION Phone: (785) 483-9164

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 10% gel - 600# hulls.
DV at 814' w/225 sxs.
CIBP at 2550'.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/17/2005 11:00 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perfs:

Swaged onto 5 1/2" - mixed and pumped 200 sxs cement with 600# hulls.
S.I.P. 1000#.
Annulus full of cement.

RECEIVED
MAY 20 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed _____

Jay Pfeifer
(TECHNICIAN)

INVOICED

DATE 05-20-05

WV NO. 2005061600

Form CP-2/3

MAY 18 2005

SOHIO PETROLEUM CO.
P.O. BOX 673
RUSSELL, KS.
CONTR ?

#30 OSWALD-WILCOX "A"

8-12-15W
SE NE NE

CTY RUSSELL

GEOL _____ FIELD FAIRPORT

E 1751 KB CM 6/1/76 CARD ISSUED 8/12/76 IP P 58 BOPD + 126BWPD
TARKIO 2398-2406

+	+	+
+	+	+
+	+	+

API 15-167-20,907

LOG	TOPS	DEPTH	DATUM
GR HAV		2295	- 544
TARKIO LS		2369	- 618
3RD TARKIO SD			
		2397	- 646
TOP		2611	- 860
HEEB		2833	-1082
LANS		2888	-1137
PENN CONG		3184	-1433
ARB		3250	-1499
TD		3263	-1512

8 5/8" 1360/125sx, 5 1/2" 3253/300sx
DST (1) 2396-2420/30-30-60-90, 688' GIP
216' O&GCM, SIP 405-506#, FP 40-80#,
81-101#
MCT - PF 2892-2932 OA A 2000, PF 2890-
94, 2914-18, 2930-34, SWB 10 BFPH, 50%
OIL, BP @ 2460 PF (TARK) 2398-2406, FRAC
17,250# SD + 7000 GW, POP

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

37AG
MAICED