

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-01789-00-00  
Spot: NWSWSE Sec/Twnshp/Rge: 5-12S-15W  
990 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: SUTTON A Well #: 1  
County: RUSSELL Total Vertical Depth: 3280 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 8100 E. 22ND N. BLDG. 300  
WICHITA, KS 67226

PROD Size: 5.5 feet: 3190  
SURF Size: 8.625 feet: 753

4106<sup>60</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/16/2005 9:00 AM  
Plug Co. License No.: 32452 Plug Co. Name: SMOKY HILLS WELL SERVICE  
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORPORATION Phone: (785) 483-9169

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 10% gel - 500# hulls - 13 sxs gel.  
CIBP at 2710'. Well squeezed 731' w/400 sxs.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/16/2005 12:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perfs:

TIH with tubing to 2600' - mixed and pumped 50 sxs cement with 200# hulls, followed with 13 sxs gel.  
Pulled up to 1400' - pumped 100 sxs cement.  
Pulled up to 820' - circulated cement with 15 sxs cement and 100# hulls.  
POOH. Topped off with 35 sxs cement.  
S.I.P. 200#. Annulus full of cement.

RECEIVED  
MAY 20 2005  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

102

Signed \_\_\_\_\_

Jay Pfeifer  
(TECHNICIAN)  
INVOICED

DATE 5-20-05

INV. NO. 2005061600

Form CP-2/3

MAY 18 2005

MAST DRILLING

#1

SUTTON 'A'

5-12-15W  
NW SW SE

Contr. MAST DRILLING

RUSSELL

County

E 1724 RB Comm.

Comp. 7-3-59

IP 28 BOPD

| Tops     | Depth | Datum | Casing                        |
|----------|-------|-------|-------------------------------|
|          |       |       | 8" 750                        |
| HEEB     | 2773  | -1019 | 5" 3190                       |
| TOR      | 2800  | -1076 | DST 2812-50/1 HR, 20' MDY     |
| KC       | 2831  | -1107 | WTR, BHP 105#                 |
|          |       |       | DST 2855-65/2 HR, 240' G, 2'  |
|          |       |       | 0, 15' H OCM, 13' M, BHP 140# |
| ARB      | 3140  | -1416 | DST 3140-50/2 HR, 50' G, 250' |
|          |       |       | CL 0, NW, BHP 800#            |
| REAG SND | 3242  | -1518 | CO 3280: WTR: PERF 3139-42:   |
| GRAN     | 3277  | -1553 | ACID 500: SWB 10 BO & 3 BWPH  |
|          |       |       |                               |
| TD       | 3280  | -1556 |                               |

|   |   |   |
|---|---|---|
| + | + | + |
| + | + | + |
| + | + | + |

FAIRPORT POOL

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS