

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-00451-00-02  
Spot: SESESE Sec/Twnshp/Rge: 33-10S-23W  
330 feet from S Section Line, 330 feet from E Section Line  
Lease Name: DIEBOLT B Well #: 4  
County: GRAHAM Total Vertical Depth: 3763 feet

Operator License No.: 33069  
Op Name: ENCORE OPERATING COMPANY  
Address: P. O. BOX 27710  
DENVER, CO 80227

PROD Size: 5.5 feet: 3763 125 SX CMT  
SURF Size: 8.625 feet: 210 175 SX CMT

# 122<sup>30</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/06/2005 11:00 AM  
Plug Co. License No.: 33346 Plug Co. Name: TR SERVICE AND RENTAL, INC.  
Proposal Rcvd. from: ROLAND NYP Company: ENCORE OPERATING COMPANY Phone: (785) 737-3242

Proposed  
Plugging  
Method:

Plugging Proposal Received By: HERB DEINES Witness Type: PARTIAL  
Date/Time Plugging Completed: 05/06/2005 12:15 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Ran tubing to 2100' - circulated with 150 sxs cement and 500# hulls.  
Pulled all tubing - squeezed 4 1/2" with 160 sxs cement.  
Max. P.S.I. 1000#. S.I.P. 500#.  
Tied to 8 5/8" x 4 1/2" annulus and squeezed 80 sxs cement with 100# hulls.  
Max. P.S.I. 500#. S.I.P. 300#.  
Total of 390 sxs 60/40 pozmix - 10% gel and 600# hulls.

Perfs:

Top	Bot	Thru	Comments
3546	3753		

RECEIVED  
MAY 20 2005  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. RGN TANK-WATER.

Plugged through: TBG

District: 04

Signed RD- Roger L. Moses  
(TECHNICIAN)

**INVOICED**

DATE 5-20-05  
INV NO. 2005061598

Form CP-2/3

MAY 18 2005

# IMAGED

IMPERIAL DRILLING

#4 DIEBOLT

33-10-23W  
SE SE SE

Contr. \_\_\_\_\_ GRAHAM \_\_\_\_\_ County

E 2329RB Comm. 7-2-54 Comp. 8-27-54 IP 70 BOPD

Tops	Depth	Datum
ANH	1812	517
HEEB	3529	-1200
LANS	3563	-1234
TD	3763	-1434

**Casing**  
 8" 210  
 5" 3763  
 DST 3589-3600/50", 17' SL OCM  
 BHP 970#: DST 3589-3603/35"  
 690' GAS, 145' MCO, 65' OC  
 SW, BHP 970#: DST 3724-38/  
 IHR, 184' GAS, 30' MUD, SPKS  
 OIL, BHP 900#: PERF 30/3228  
 -33: 2 GOPH: SWB 1 1/4 BO & 5  
 DIEBOLT POOL BWPB: PLUG 3700  
 2 GOPH: SWB 1 1/4 BO & 5  
 BWPB: PLUG 3700: 9/  
 3597-99: ACID 100: SWB  
 5 BO & 15 BWPB:

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS