

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-047-20726-00-00  
Spot: E2E2SE Sec/Twnshp/Rge: 33-24S-16W  
1120 feet from S Section Line, 330 feet from E Section Line  
Lease Name: MEYERS Well #: 2-A  
County: EDWARDS Total Vertical Depth: 4419 feet

Operator License No.: 33260  
Op Name: THE WARREN CORPORATION  
Address: 50 PENN PLACE, SUITE 410  
OKLAHOMA CITY, OK 73118

PROD Size: 4.5 feet: 4419 WITH 125 SX CMT  
SURF Size: 8.625 feet: 1091 WITH 550 SX CMT

*#143<sup>62</sup>*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/11/2005 2:30 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Revd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: SAND TO 4320' & 4 SX CMT. PLUG AT 1150' WITH 10 SX GEL - 300# HULLS - 50 SX CMT. PLUG AT 360' WITH 40 SX CMT W/300# HULLS. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/11/2005 5:18 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

ANHYDRITE @ 1100'. SANDED TO BOTTOM TO 4320' & 4 SX CMT WITH DUMP BAILER. SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG @ 1150' WITH 10 SX GEL - 50 SX CMT WITH 300# HULLS. 2ND PLUG AT 360' WITH 40 SX CMT WITH 300# HULLS. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4380	4384		
4373	4376		

RECEIVED  
MAY 23 2005  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2260' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed Richard M. Lacey  
(TECHNICIAN)

MAY 16 2005

*MD*

INVOICED  
DATE 5-23-05  
INV. NO. 2005061613

Form CR-2/3 *[Signature]*