

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-21482-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 33-24S-16W
2310 feet from S Section Line, 2310 feet from E Section Line
Lease Name: MEYERS Well #: 1
County: EDWARDS Total Vertical Depth: 4430 feet

Operator License No.: 33260
Op Name: THE WARREN CORPORATION
Address: 50 PENN PLACE, SUITE 410
OKLAHOMA CITY, OK 73118

CIBP Size: feet: 4234 WITH 4 SX CMT
PROD Size: 4.5 feet: 4424 WITH 135 SX CMT
SURF Size: 8.625 feet: 335 WITH 250 SX CMT

#143 98

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/10/2005 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: CIBP @ 4234' & 4 SX CMT. PLUG AT 1150' WITH 15 SX GEL & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: PARTIAL
Date/Time Plugging Completed: 05/10/2005 12:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

CMT RETAINER @ 4314'. ANHYDRITE @ 1110'. SET CIBP @ 4234' & 4 SX CMT WITH BAILER. SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 1150' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 360' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4374	4378		
4324	4344		
4284	4288		

RECEIVED
MAY 23 2005
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2420' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

MAY 16 2005

MP

Signed Richard M. Lacey
(TECHNICIAN)

INVOICED

DATE 5-23-05

INV. NO. 200506143

Form CP-2/3