

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-01543-00-00  
Spot: NWNWSE Sec/Twnshp/Rge: 12-25S-13W  
2970 feet from N Section Line, 2310 feet from E Section Line  
Lease Name: NORTH LEESBURG UNIT Well #: 301  
County: STAFFORD Total Vertical Depth: 4128 feet

Operator License No.: 6679  
Op Name: SHORT, W.D. AND MARJORIE D/B/A SH  
Address: PO BOX 1  
OXFORD, KS 67119

CIBP Size: feet: 3000 WITH 2 SX CMT  
CIBP Size: feet: 3104  
CIBP Size: feet: 3760  
CIBP Size: feet: 4100  
PROD Size: 7 feet: 4104 WITH 300 SX CMT  
SURF Size: 10.75 feet: 458 WITH 400 SX CMT

#13416

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/12/2005 12:00 PM  
Plug Co. License No.: 30437 Plug Co. Name: UNITED CEMENTING AND ACID CO., INC.  
Proposal Rcvd. from: MIKE ANSTINE Company: W.D. SHORT Phone: (620) 455-3576

Proposed Plugging Method: CIBP @ 3000' WITH 2 SX CMT. CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/12/2005 4:12 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

ANHYDRITE @ 727'. SET CIBP @ 3000' WITH 2 SX CMT ON TOP. SHOT PIPE @ 850'.  
PRESSURED 7" TO 750 PSIG FOR 30 MINUTES. NO HOLES IN PIPE. RAN CEMENT  
BOND LOG TO 800'. NO CMT. PERFORATED 7" @ 800'. PUMPED 450 SX CMT  
DOWN 7" CIRUCLATING CMT TO SURFACE UP 10 3/4" X 7" ANNULUS.

Perfs:

Top	Bot	Thru	Comments
4054	4070		
3771	3781		
3741	3751		
3728	3732		
3697	3703		
3644	3649		
3066	3074		

INVOICED  
DATE 5-23-05  
REV. NO. 2005061611  
RECEIVED  
MAY 23 2005  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY UNITED CEMENTING. NO CASING RECOVERED.

Plugged through: CSG

District: 01

MAY 16 2005

Signed Richard W. Lacey  
(TECHNICIAN)