

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-30156-00-00  
Spot: NESE Sec/Twnshp/Rge: 8-34S-12W  
2031 feet from S Section Line, 660 feet from E Section Line  
Lease Name: COOK-HARDTNER Well #: 1  
County: BARBER Total Vertical Depth: 4755 feet

Operator License No.: 5364  
Op Name: BEREN CORPORATION  
Address: P.O. BOX 20380  
WICHITA, KS 67208

PROD Size: 4.5 feet: 4779 WITH 275 SX CMT  
SURF Size: 8.625 feet: 414 WITH 300 SX CMT

#5454

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/19/2005 1:45 PM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND BACK BOTTOM. PLUG AT 600' WITH 10 SX GEL & 40 SX CMT. PLUG AT 430' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT

Plugging Proposal Received By: KEN JEHLIK  
Date/Time Plugging Completed: 05/19/2005 3:00 PM

WitnessType: COMPLETE (100%)  
KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

SANDED BACK TO 4470' & 4 SX CMT WITH DUMP BAILER. 1ST PLUG AT 618' WITH 10 SX GEL & 40 SX CMT. 2ND PLUG AT 450' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4736	4739		
4528	4532		


INVOICED  
DATE 5-23-05  
INV. NO. 2005061602

RECEIVED  
MAY 23 2005  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2409' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

PIRT II Jerry W. Stapleton  
(TECHNICIAN)

Form CP-273