

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-151-21356-00-00  
Spot: SESE Sec/Twnshp/Rge: 33-28S-12W  
660 feet from S Section Line, 660 feet from E Section Line  
Lease Name: PAINE - A Well #: 1  
County: PRATT Total Vertical Depth: 4656 feet

Operator License No.: 30705  
Op Name: YOUNGER ENERGY COMPANY  
Address: 453 S. WEBB RD., STE 100  
WICHITA, KS 67207

CIBP Size: feet: 4250  
PROD Size: 4.5 feet: 4637 WITH 150 SX CMT  
SURF Size: 8.625 feet: 449 WITH 300 SX CMT

32  
\$151

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/18/2005 10:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: SAND TO 4170' & 4 SX CMT. PLUG AT 700' WITH 10 SX GEL & 50 SX CMT. PLUG AT 480' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/18/2005 10:49 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 4170' & 4 SX CMT WITH DUMP BAILER. PUMPED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 700' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 480' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. GOOD CIRCULATION THROUGH OUT JOB.

Perfs:

Top	Bot	Thru	Comments
4259	4275		
4222	4224		

RECEIVED  
MAY 23 2005  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2435' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED  
MAY 20 2005  
KCC Dodge City

Signed

Richard W. Lacey  
(TECHNICIAN)

INVOICED  
DATE 5.23.05  
INV. NO. 2005061615