

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22768-00-00
Spot: NENWNWSE Sec/Twnshp/Rge: 30-32S-11W
2420 feet from S Section Line, 2150 feet from E Section Line
Lease Name: BENNETT Well #: 1
County: BARBER Total Vertical Depth: 5368 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N. MARKET, SUITE 1000
WICHITA, KS 67202

CIBP Size: feet: 4250 WITH 2 SX CMT
CIBP Size: feet: 4450
PROD Size: 4.5 feet: 4826 WITH 150 SX CMT
SURF Size: 10.75 feet: 267 WITH 175 SX CMT

\$174.46

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Revd. from: CARL W DURR Company: _____ Phone: (620) 886-5606

Proposed Plugging Method: SAND BACK TO 4200', PLACE 4 SX ON TOP W/DUMP BAILER. 1st PLUG @ 600' CIRCULATE THROUGH TUBING 10 SX GEL & 50 SX 60/40 6% GEL. 2nd PLUG @ 300' CIRCULATE 75 SX SAME CMT. 3rd PLUG @ 40' CIRCULATE 20 SX SAME CMT TO SURFACE. CUT & CAP 10-3/4" 3' BELOW GROUND LEVEL.

Plugging Proposal Received By: STEVE DURRANT WitnessType: NONE
Date/Time Plugging Completed: 05/12/2005 5:00 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

1ST PLUG CIBP @ 4250' & 2 SX CMT. 2ND PLUG LOAD HOLE WITH 10 SX GEL @ 600' & PUMP 60 SX CMT. 3RD PLUG PULL TO 270' & PUMP 50 SX CMT. 4TH PLUG PULL TO 40' & CIRCULATE CMT TO 0'.

Perfs:


Top	Bot	Thru	Comments
4566	4576		
4316	4330		
4282	4283		

RECEIVED
MAY 23 2005
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3200' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Steve Durrant
(TECHNICIAN)

INVOICED

DATE 5-23-05
INV. NO. 200506164