

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-25410-00-00  
Spot: W2SWSE Sec/Twnshp/Rge: 6-13S-16W  
610 feet from S Section Line, 2200 feet from E Section Line  
Lease Name: CONNIE Well #: 6-3  
County: ELLIS Total Vertical Depth: 3693 feet

Operator License No.: 33335  
Op Name: IA OPERATING, INC.  
Address: 900 N TYLER ROAD #14  
WICHITA, KS 67212

SURF Size: 8.625 feet: 1170

*\$120<sup>02</sup>*

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/19/2005 3:15 PM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: ANDY DINKEL Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Order 210 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES Witness Type: NONE  
Date/Time Plugging Completed: 05/19/2005 6:15 PM KCC Agent: HERB DEINES

Actual Plugging Report:

Perfs:

1st. Plug at 3490' w/25 sxs.  
2nd. Plug at 1225' w/50 sxs.  
3rd. Plug at 800' w/100 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.  
Mousehole with 10 sxs.

RECEIVED  
MAY 23 2005  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed   
(TECHNICIAN)

INVOICED

DATE 5-23-05

INV. NO. 2005061608

MAY 20 2005