

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-21871-00-01
Spot: NWSW Sec/Twnshp/Rge: 32-29S-12W
1980 feet from S Section Line, 4620 feet from E Section Line
Lease Name: BRUBAKER Well #: 1
County: PRATT Total Vertical Depth: 4716 feet

Operator License No.: 30380
Op Name: HUPFER OPERATING, INC.
Address: PO BOX 216
HAYS, KS 67601

CIBP Size: feet: 4600
PROD Size: 5.5 feet: 4711 WITH 200 SX CMT
SURF Size: 8.625 feet: 266 WITH 175 SX CMT

#153²⁷

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/11/2005 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 4250' & 5 SX CMT. PLUG AT 730' WITH 10 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/11/2005 11:52 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED BOTTOM TO 4250' & 5 SX CMT ON TOP OF SAND WITH DUMP BAILER. SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 730' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4461 | 4480 | | |
| 4283 | 4288 | | |

RECEIVED
MAY 23 2005
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND ACID. RECOVERED 2420' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

MAY 16 2005
AP

INVOICED
DATE 5-23-05
TEL. NO. 2005061607

[Signature]
Form CP 233