

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-21633-00-00
Spot: N2SEW Sec/Twnshp/Rge: 22-19S-20W
3630 feet from S Section Line, 3300 feet from E Section Line
Lease Name: BANNISTER Well #: 1
County: RUSH Total Vertical Depth: 4356 feet

Operator License No.: 5316
Op Name: FALCON EXPLORATION, INC.
Address: 155 N. MARKET, STE. 1020
WICHITA, KS 67202

MSCC Size: feet: 670 WITH 150 SX CMT
PROD Size: 5.5 feet: 4355 WITH 200 SX CMT
SURF Size: 8.625 feet: 299 WITH 160 SX CMT

#141 57

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/16/2005 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: LEON KUHN Company: FALCON EXPLORATION Phone: (785) 483-1559

Proposed Plugging Method: PUMP DOWN 5 1/2" CASING WITH 100# HULLS - 30 SX CMT W/200# HULLS MIXED IN - 34 SX GEL - 90 SX CMT. CHECK PRESSURES. CHECK BACKSIDE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/16/2005 11:40 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PUMPED DOWN 5 1/2" CASING WITH 100# HULLS - 30 SX CMT W/200# HULLS MIXED IN - 34 SX GEL - 90 SX CMT. MAXIMUM PRESSURE 1600 PSIG. INITIAL SHUT IN PRESSURE 1000 PSIG. PRESSURED 8 5/8" X 5 1/2" ANNULUS TO 500 PSIG WITH 1 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4345	4349		
4339	4342		

RECEIVED
MAY 23 2005
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

RECEIVED
MAY 20 2005
KCC Dodge City

Signed Richard W. Lacey
(TECHNICIAN)

INVOICED
DATE 5-23-05
INV. NO. 2005061604

Form CR-173