

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-21720-00-00
Spot: SENWNWNW Sec/Twnshp/Rge: 16-30S-15W
560 feet from N Section Line, 560 feet from W Section Line
Lease Name: LEE Well #: 1-16
County: BARBER Total Vertical Depth: 4899 feet

Operator License No.: 5147
Op Name: BEREDCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

CIBP Size: feet: 4350
CIBP Size: feet: 4450
CIBP Size: feet: 4540
CIBP Size: feet: 4545
PROD Size: 5.5 feet: 4899 WITH 200 SX CMT
SURF Size: 8.625 feet: 503 WITH 300 SX CMT

#159²²

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/16/2005 2:20 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JASON BRUNS Company: BEREDCO Phone: (620) 886-2080

Proposed Plugging Method: SAND BACK TO 4120' & 5 SX CMT. PLUG AT 1200' WITH 10 SX GEL & 400# HULLS MIXED IN 50 SX CMT. PLUG AT 530' WITH 50 SXC MT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/16/2005 4:00 PM KCC Agent: GREG PATTERSON

Actual Plugging Report:

PBTD 4250'. SAND TO 4120' & 5 SX CMT. 1ST PLUG AT 1216' WITH 10 SX GEL & 400# HULLS MIXED IN 50 SX CMT. 2ND PLUG AT 520' WITH 5 SX GEL & 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4622	4626		
4594	4602		
4560	4566		
4495	4506		
4198	4202		

INVOICED
DATE 5-23-05
TEL. NO. 2005061601
RECEIVED
MAY 23 2005
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 3000' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Greg Patterson
(TECHNICIAN)