

STATE OF KANSAS
STATE CORPORATION
COMMISSION
130 South Market Room 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R. 82-3-117

API NUMBER 15-033-21029 - 00 - 00

LEASE NAME Acres

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 60 days.

WELL NUMBER 2-21

2310 Ft. from N / S Section Line

1900 Ft. from E / W Section Line

LEASE OPERATOR CLX Oil & Gas, LLC

SEC. 21 TWP. 32S RGE. 18 (E) or AM

ADDRESS 518 17th St., Suite 745, Denver, CO 80202

COUNTY Cornace

PHONE # 303 825-7080 OPERATOR'S LICENSE NO. 33455

Date Well ^{Spud} Completed 9/16/1999

Character of Well Good Gas

Plugging Commenced 4/18/2005

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4/20/2005

The plugging proposal was approved on 4/15/2005 (date)

by Richard Lacey (KCC District Agent's Name).

is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation _____ Depth to Top 5080 Bottom 5101 T. D. 5430

*KCC
BEM
5-19-05
RBDMS
CP 2/3*

Show depth and thickness of all water, oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				13 3/8	80	None
				8 5/8	671	None
				5 1/2	5420	3200

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Pull tubing, set CIBP @ 5000', dump 2 sacks cement with dump bailer 4/19 - stretch and cut off casing @ 3200', pull And lay down casing 4/20 - run tubing to 1150', load hole with 15 gel, pump 50 sacks cement, pull tubing to 700', pump 50 sacks, pull to 300', pump 40 sacks, pull to 40', circulate to surface with 60/40 poz, 4% gel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105


Address P.O. Box 187, 107 W. Fowler, Medicine Lodge, KS 67104

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: CLX Oil & Gas LLC

STATE OF Kansas COUNTY of Barber, ss.

John Swinford (Employee of Operator) or (Operator) of above described well, being

first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filled that the same are true and correct, so help me God.



(Signature) John Swinford

(Address) P.O. Box 187, Medicine Lodge, KS 67104

SUBSCRIBED AND SWORN TO before me this 16 day of May 2005

Glenda Morrison
Notary Public

My Commission Expires: November 30, 2006

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 19 2005
CONSERVATION DIVISION
WICHITA, KS