

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-175-20394-00-01

LEASE NAME Mildred Lemert

WELL NUMBER 1-34 SWD

1618  
1450 Ft. from S Section Line *KCC*

1917  
505 Ft. from E Section Line *BEN*

SEC. 34 TWP. 32 RGE. 33W (E) or (W) *ABDM*

COUNTY Seward *CP2/3*

Date Well Completed 1979 *GPS*

Plugging Commenced 03/18/05

Plugging Completed 03/18/05

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Chesapeake Operating, Inc.

ADDRESS P. O. Box 18496, Oklahoma City, OK 73154-0496

PHONE# (405) 848-8000 OPERATORS LICENSE NO. 32334

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12/2004 (date)

by David Williams (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Injection Council Grove - Depth to Top 2526 Bottom 3032 T.D. 3080'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8	600'	
				5-1/2	3069	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set  
MIRU Allied. pump 500# cs hulls. mix 300# cs hulls w/215 sx 60/40 poz. pump down csg. SD.  
hook up to surf. csg. pump 5 sx 60/40 poz. pressure to 300#. hook up to production csg.  
full. cut off wellhead. RDMO. weld on cap. clean up location

Name of Plugging Contractor Allied Cementing Co., Inc. License No. \_\_\_\_\_

Address P. O. Box 31, Russell, KS 67665 (785) 483-2626

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Chesapeake Operating, Inc.

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Jim Reisch (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Barbara J. Bale for Jim Reisch  
Jim Reisch

(Address) P.O. Box 18496, Okla. City, OK 73154

SUBSCRIBED AND SWORN TO before me this 20th day of May, 19 2005

Quentin A. Morris  
Notary Public

My Comm. Expires 11/27/08  
SEAL OF PUBLIC  
Notary Public  
State of Oklahoma  
Commission # 00018352 Expires 11/27/08

RECEIVED  
MAY 23 2005  
KCC WICHITA

# ALLIED CEMENTING CO., INC.

19089

Federal Tax I.D.# ~~XXXXXXXXXX~~

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:

DAKLEY

DATE <u>3-17-05</u>	SEC <u>34</u>	TWP. <u>32S</u>	RANGE <u>33W</u>	CALLED OUT	ON LOCATION <u>10:45 AM</u>	JOB START <u>11:15 AM</u>	JOB FINISH <u>11:45 AM</u>
LEASE <u>LEMERT</u>	WELL # <u>1-34</u>	LOCATION <u>Sublette 15S-1W-4 1/2 S</u>	COUNTY <u>SEWARD</u>	STATE <u>KS</u>			

OLD OR NEW (Circle one)

CONTRACTOR NONE OWNER SAME

TYPE OF JOB OLD HOLE

HOLE SIZE \_\_\_\_\_ T.D. \_\_\_\_\_

CASING SIZE 5 1/2" DEPTH \_\_\_\_\_

TUBING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_

DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_

TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_

PRES. MAX \_\_\_\_\_ MINIMUM \_\_\_\_\_

MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_

CEMENT LEFT IN CSG. \_\_\_\_\_

PERFS. \_\_\_\_\_

DISPLACEMENT \_\_\_\_\_

CEMENT

AMOUNT ORDERED 250 SKS 60/40 POZ 686EL

800# Hulls

USED 220 SKS 60/40 POZ 686EL 800# Hulls

COMMON	<u>132 SKS</u>	@	<u>9 10</u>	<u>1201.20</u>
POZMIX	<u>88 SKS</u>	@	<u>4 10</u>	<u>360.80</u>
GEL	<u>11 SKS</u>	@	<u>11</u>	<u>121</u>
CHLORIDE		@		
ASC		@		

### EQUIPMENT

PUMP TRUCK CEMENTER TERRY

# 191 HELPER WAYNE MAX

BULK TRUCK

# 386 DRIVER LONNIE

BULK TRUCK

# \_\_\_\_\_ DRIVER \_\_\_\_\_

Hulls 800#	@	<u>20 1/2</u>	<u>160 1/2</u>
HANDLING	<u>271 SKS</u>	@	<u>1 35</u>
MILEAGE	<u>054 PER SK/ MILE</u>		<u>365.85</u>
TOTAL			<u>406.50</u>

### REMARKS:

MIX 500# Hulls 215 SKS CEMENT  
WITH 300# Hulls. NO PRESSURE  
PIPE WAS FULL. HOOK ON  
BACKSIDE MIX 55 SKS CEMENT  
PRESSURE TO 300 PSI. SHUT IN

THANK YOU

CHARGE TO: CHESAPEAKE OPERATING

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

### SERVICE

DEPTH OF JOB \_\_\_\_\_

PUMP TRUCK CHARGE \_\_\_\_\_ 580 1/2

EXTRA FOOTAGE \_\_\_\_\_ @ \_\_\_\_\_

MILEAGE 30 @ 4 1/2 120 1/2

MANIFOLD \_\_\_\_\_ @ \_\_\_\_\_

TOTAL 700 1/2

### PLUG & FLOAT EQUIPMENT

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

TOTAL \_\_\_\_\_

To Allied Cementing Co., Inc. **KCC WICHITA**

You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE [Signature]

PRINTED NAME \_\_\_\_\_

TAX \_\_\_\_\_

TOTAL CHARGE \_\_\_\_\_

DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS