

**Notice:** Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117**

Form CP-4  
December 2003  
**Type or Print on this Form**  
Form must be Signed  
All blanks must be Filled

Lease Operator: John O. Farmer, Inc.  
 Address: PO Box 352, Russell KS 67665  
 Phone: (785) 483-3144 Operator License #: 5135  
 Type of Well: Oil Docket #: \_\_\_\_\_  
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
 The plugging proposal was approved on: \_\_\_\_\_ (Date)  
 by: District #1 (KCC District Agent's Name)  
 Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
 Producing Formation(s): List All (If needed attach another sheet)  
Simpson Sand Depth to Top: 4610 Bottom: 4615 T.D. 4703  
Marmaton Depth to Top: 4323 Bottom: 4328 T.D. 4408  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-151-21,449-0000  
 Lease Name: Kinzie  
 Well Number: 5  
 Spot Location (QQQQ): \_\_\_\_\_ - NW - NW - NW  
330 Feet from  North /  South Section Line  
330 Feet from  East /  West Section Line  
 Sec. 23 Twp. 29S S. R. 13  East  West  
 County: Pratt  
 Date Well Completed: 7/84  
 Plugging Commenced: 05-12-05  
 Plugging Completed: 05-13-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				13 3/8	220	
				8 5/8	992	
				5 1/2	4727	2750

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


Checked hole sand at 4270', bailed 5 sacks cement, ripped pipe at 3050', 2820', 2750', pulled to 1030', pumped 15 gel & 50 sacks cement, pulled to 300', pumped 40 sacks, pulled to 40', pumped 20 sacks.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925  
 Address: 401 West Main, Lyons, KS 67554  
 Name of Party Responsible for Plugging Fees: John O. Farmer, Inc.  
 State of Kansas County, Russell, ss.

**RECEIVED  
MAY 23 2005  
KCC WICHITA**

John O. Farmer IV (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.  
 (Signature) John O. Farmer IV  
 (Address) P.O. Box 352, Russell, KS 67665

SUBSCRIBED and SWORN TO before me this 20th day of May, 20 05  
Margaret A. Schulte My Commission Expires: \_\_\_\_\_  
 Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*B...*

# ALLIED CEMENTING CO., INC. 20520

Federal Tax I.D. ~~XXXXXXXXXX~~

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:  
MEDICINE LODGE

DATE <u>5-13-05</u>	SEC. <u>23</u>	TWP. <u>29S</u>	RANGE <u>13W</u>	CALLED OUT <u>11:30 am</u>	ON LOCATION <u>1:30 pm</u>	JOB START <u>2:40 pm</u>	JOB FINISH <u>3:45 pm</u>
LEASE <u>KINDLE</u>	WELL # <u>5</u>	LOCATION <u>SANDY, KS, NORTH ON 281 TO THE</u>		COUNTY <u>MAHAR</u>	STATE <u>KS</u>		
OLD OR NEW (Circle one)		<u>1ST PNE LINE GOING WEST, 1 1/2 W, 3/4 SIDE</u>					

CONTRACTOR QUALITY W.S.  
 TYPE OF JOB O.H.P.  
 HOLE SIZE 7 1/8" T.D. 1,030'  
 CASING SIZE 5 1/2 DEPTH 1,030'  
 TUBING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_  
 DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_  
 TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_  
 PRES. MAX 100 MINIMUM \_\_\_\_\_  
 MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_  
 CEMENT LEFT IN CSG. \_\_\_\_\_  
 PERFS. \_\_\_\_\_  
 DISPLACEMENT FRESH WATER

**EQUIPMENT**  
 PUMP TRUCK CEMENTER BILL M.  
 # 360 HELPER LARRY D.  
 BULK TRUCK \_\_\_\_\_  
 # 356 DRIVER DEWY S.  
 BULK TRUCK \_\_\_\_\_  
 # \_\_\_\_\_ DRIVER \_\_\_\_\_

**REMARKS:**  
LOAD HOLE WITH 15 SX GEL, PUMP 50 SX  
CEMENT, DISPLACE WITH 18,93 bbl. WATER,  
2nd PLOG (300') PUMP 40 SX CEMENT,  
DISPLACE WITH 2,35 bbl. WATER, 3rd  
PLOG (40' TO SURFACE) LOAD HOLE, PUMP  
20 SX CEMENT, WASH PUMP & LINES.

CHARGE TO: JOHN Q. FARMER  
 STREET \_\_\_\_\_  
 CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

To Allied Cementing Co., Inc.  
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE Joe Maes

OWNER JOHN Q. FARMER  
**CEMENT**  
 AMOUNT ORDERED 110 SX 60' 40' 6" 15 SX GEL

COMMON	<u>66 A</u>	@	<u>8.70</u>	<u>574.20</u>
POZMIX	<u>44</u>	@	<u>4.70</u>	<u>206.80</u>
GEL	<u>21</u>	@	<u>14.00</u>	<u>294.00</u>
CHLORIDE		@		
ASC		@		
		@		
		@		
		@		
		@		
		@		
		@		
		@		
		@		
HANDLING	<u>131</u>	@	<u>1.60</u>	<u>209.60</u>
MILEAGE	<u>20 X 131 X .06</u>			<u>159.00</u>
	<u>M. in chg</u>			<u>TOTAL 1464.60</u>

**SERVICE**  
 DEPTH OF JOB 1,030'  
 PUMP TRUCK CHARGE 600.00  
 EXTRA FOOTAGE @ \_\_\_\_\_  
 MILEAGE 20 @ 5.00 100.00  
 MANIFOLD @ \_\_\_\_\_  
 @ \_\_\_\_\_  
 @ \_\_\_\_\_  
 @ \_\_\_\_\_  
 @ \_\_\_\_\_  
 TOTAL 700.00

**PLUG & FLOAT EQUIPMENT**  
 @ \_\_\_\_\_  
 @ \_\_\_\_\_  
 @ \_\_\_\_\_  
 @ \_\_\_\_\_  
 @ \_\_\_\_\_  
 @ \_\_\_\_\_  
 TOTAL \_\_\_\_\_

TAX \_\_\_\_\_  
 TOTAL CHARGE \_\_\_\_\_  
 DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

PRINTED NAME JOE MAES

**COPY**

RECEIVED  
 MAY 23 2005  
 KCC WICHITA