

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
December 2003
**Type or Print on this Form
Form must be Signed
All blanks must be Filled**

Lease Operator: Murfin Drilling Company, Inc.
 Address: 250 N. Water, Suite 300
 Phone: (316) 267-3241 Operator License #: 30606
 Type of Well: Oil Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: 5/11/05 (Date)
 by: Darrell Dipman w/ KCC in Hays, KS (KCC District Agent's Name)
 Is AGO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
4178-86, 4229-32, 4244-46, Depth to Top: _____ Bottom: _____ T.D. _____
4260-69, 4304-09, 4314-14.5 Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 616/60 153 - 05300-00-01
 Lease Name: Texaco Cahoj Unit
 Well Number: #57
 Spot Location (QQQQ): C - NW - NE - _____
4620 Feet from North / South Section Line
1980 Feet from East / West Section Line
 Sec. 20 Twp. 1S S. R. 34 East West
 County: Rawlins
 Date Well Completed: 6/16/60 original 6-9-1986 *KCC*
 Plugging Commenced: 5/11/05 *5/26/05 RBMS CP 2/3*
 Plugging Completed: 5/11/05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	Surface	372	8 5/8	372	0
	Production	Surface	4386	5 1/2	4386	0


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

TIH w/tbg to 2500'. RU Swift, Pumped 135 sxs SMD cmt & 450# hulls, no circ. Pulled tbg to 1200'. Pumped 70 sxs SMD & 450# hulls & circ cmt to surface. Only rec approx 2 BO. TOH w/tbg. Top off 5 1/2" csg w/10 sx & csg stayed full. Hooked up to 8 5/8" csg. Pumped 20 sx cement. Max press 300#. SI @ 100#. Well P/A. Witnessed & approved by Darrell Dipman w/KCC.

Name of Plugging Contractor: Murfin Drilling Company, Inc. License #: 30606
 Address: 250 N. Water, Suite 300 ; Wichita, KS 67202
 Name of Party Responsible for Plugging Fees: Murfin Drilling Company, Inc.
 State of Kansas County, Sedgwick, ss.
Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
 (Address) 250 N. Water, Suite 300; Wichita, KS 67202



My Appt. Expires 24th day of May 20 05
Susan Brady My Commission Expires: 11-4-07
 Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
MAY 25 2005
KCC WICHITA

[Handwritten signature]