

Amended

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Citation Oil & Gas Corp.

Address: P.O. Box 690688; Houston, TX 77269

Phone: (281) 517-7194 Operator License #: _____

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 2/2/2004 (Date)

by: Bruce Bayse (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)
LKC Depth to Top: 3832' Bottom: 4015' T.D. 4030'

_____ Depth to Top: _____ Bottom: _____ T.D. _____

_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-065-03277-00-00

Lease Name: Elrick Unit

Well Number: 12-1

Spot Location (QQQQ): _____ - SW - SW - NE

2970 Feet from North / South Section Line

2310 Feet from East / West Section Line

Sec. 10 Twp. 10 S. R. 25 East West

County: Graham

Date Well Completed: _____

Plugging Commenced: 4/26/2004

Plugging Completed: 4/26/2004

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
LKC	Oil/Water	0'	209'	8-5/8"	209'	N/A
		0'	4029'	5-1/2"	4029'	N/A

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

M&P'd 30 bbls gelled FW 3520' - 2300'; perf'd 2300' - 2301'; pumped 100 sx 60/40 Poz with 10% gel 2300' - 1300'

Perf'd 1300' - 1301'; pumped 115 sx 60/40 Poz

Pumped 15 sx 60/40 Poz inside 5-1/2" x 8-5/8" annulus and RDMO

Well Plugged and Abandoned 4/27/2004

Name of Plugging Contractor: TR Service and Rental, Inc. License #: 33346

Address: Unknown - I have been unable to locate an address for this company

RECEIVED
MAY 26 2005
KCC WICHITA


Name of Party Responsible for Plugging Fees: Citation Oil & Gas Corp.

State of Texas County, Harris, ss.

Citation Oil & Gas corp. (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Debra Harris

(Address) P.O. Box 690688, Houston, Texas 77269-0688



SUBSCRIBED and SWORN TO before me this 23rd day of May, 20 05

Renee Harrell My Commission Expires: 3-2-07

Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Bm