

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Encore Operating Company
Address: PO Box 27710 Denver, CO 80227
Phone: (303) 595-9251 Operator License #: 33069
Type of Well: OIL Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (if SWD or ENHR)
The plugging proposal was approved on: May 6, 2005 (Date)
by: Roger Moses (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
LKC Depth to Top: 3546 Bottom: 3733 T.D. 3763
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-065-00451-00-02
Lease Name: Diebolt B
Well Number: 4
Spot Location (QQQQ): SE - SE - SE -
330 Feet from North / South Section Line
330 Feet from East / West Section Line
Sec. 33 Twp. 10 S. R. 23 East West
County: Graham
Date Well Completed: July 1954
Plugging Commenced: May 6, 2005
Plugging Completed: May 6, 2005

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface CSG	0	210'	8 5/8"		none
	Producing Csg	0	3763'	5 1/2"		none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


Ran tubing to 2100' circulated 150 sks of 60/40 w/10% Gel and 500#'s of hulls to surface. Pulled tubing pumped 160 sks of cement down 5 1/2" casing @ 1000#'s ISIP 500#'s. Pumped 80 sks of cement and 100#'s of hulls down the 8 5/8" casing @ 500#'s ISIP 300#'s. Plug down @ 12:15 pm

Name of Plugging Contractor: Alliance Well Service License #: 33346
Address: _____
Name of Party Responsible for Plugging Fees: Encore Operating Company
State of Colorado County, Denver, ss.

RECEIVED
MAY 26 2005
KCC WICHITA

Roland Nyp (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Roland Nyp
(Address) 804 MAIN STOCKTON, KS 67669
SUBSCRIBED and SWORN TO before me this 23rd day of May, 2005
Steve R Nyp My Commission Expires: Sept. 30, 2008
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

bu