

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Encore Operating Company

Address: PO Box 27710 Denver, CO 80227

Phone: (303) 595-9251 Operator License #: 33069

Type of Well: ENHR Docket #: E09110-0003
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: April 4, 2005 (Date)

by: Pat Staab (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

LKC Depth to Top: 3716 Bottom: 3841 T.D. 3860
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-065-03171-00-03

Lease Name: Diebolt LKC Unit

Well Number: 8-1

Spot Location (QQQQ): - SE - SE - SW

330 Feet from North / South Section Line

2970 Feet from East / West Section Line

Sec. 21 Twp. 10 S. R. 23 East West

County: Graham

Date Well Completed: _____

Plugging Commenced: April 4, 2005

Plugging Completed: April 4, 2005

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface Csg	0	235'	10 3/4"		none
	Producing Csg	0	3885'	5 1/2"		none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran tubing to 2100', circulated 285 sacks of 60/40 Poz w/10% Gel, 1 1/4# Flo-seal and 500#'s of hulls to surface. Pulled tubing and pumped 50 sacks of cement down 5 1/2" casing, max pressure 600#'s ISIP 500#'s. Pumped 65 sacks cement and 100#'s of hulls down 10 3/4" casing, max. pressure 200#'s ISIP 50#' Plug down @ 12:30 p.m.

Name of Plugging Contractor: TR Service and Rental License #: 33346 **RECEIVED**

Address: Ellis, Kansas **MAY 26 2005**

Name of Party Responsible for Plugging Fees: Encore Operating Company **KCC WICHITA**

State of Colorado County, Denver, ss.

Roland Nyp (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Roland Nyp

(Address) 804 MAIN STOCKTON KS 67669



SUBSCRIBED and SWORN TO before me this 15th day of April, 2005

Irene R Nyp My Commission Expires: 9-30-08
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Handwritten mark