

API NUMBER 15-137-20,430-00-00

LEASE NAME Jacobs

TYPE OR PRINT

NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

WELL NUMBER 1

2990 Ft. from S Section Line

370 Ft. from E Section Line

SEC. 9 TWP. 5S RGE. 22W (NE) or (W)

COUNTY Norton

Date Well Completed 3/23/05

Plugging Commenced 2:30PM 3/23/05

Plugging Completed 5:00PM 3/23/05

LEASE OPERATOR BLACK DIAMOND OIL, INC.

ADDRESS P.O. Box 641 Hays, KS 67601

PHONE# (785) 625-5891 OPERATORS LICENSE NO. 7076

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3/22/05

(date)

by Herb Deines

(KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation None Depth to Top \_\_\_\_\_ Bottom T.O. 3584

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	<b>RECEIVED</b>	Surface	226	8 5/8	225.99	None
	<b>MAY 27 2005</b>					
	<b>KCC WICHITA</b>					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, - from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set

1st Plug @ 1725' w/25sks 10sks In Mouse Hole Circulated 1st Plug 30 Minutes W/52 Vis Mud

2nd Plug @ 1000' w/100sks 15sks In Rat Hole Plugs displaced with mud

3rd Plug @ 225' w/40sks Total 200sks 60/40Poz 6%Gel W/1/4#CF/sk By Allied Cementing

4th Plug @ 40' w/10sks Completed @ 5:00PM 3/23/05

Name of Plugging Contractor Discovery Drilling Co., Inc. License No. 31548

Address P.O. Box 763 Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Black Diamond Oil

STATE OF Kansas COUNTY OF Ellis, ss.


Kenneth Vehige

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 641



Subscribed and sworn to before me this 23rd day of May, 2005

Verda M. Brin  
 Notary Public

My Commission Expires: 7-18-07

USE ONLY ONE SIDE OF EACH FORM

[Signature]