

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2070  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R. 82-3-117

API NUMBER 15-051-25382-00-00

LEASE NAME Anna Seibel

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Comm. Div.  
office within 30 days.

WELL NUMBER 1

4,950 Ft. from 8 Section Line

4,950 Ft. from 8 Section Line

SEC. 16 TWP. 14 N. R. 20 (N) or (W)

COUNTY Ellis

Date Well Completed 4-21-05

Plugging Commenced 4-22-05

Plugging Completed 4-22-05

LEASE OPERATOR R.P. Nixon Operations, Inc.

ADDRESS 207 W. 12th, Hays, KS 67601

PHONE (785) 628-3834 OPERATORS LICENSE NO. 5252

Character of Well D & A

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-10-03

(date)

by Bruce Basye

(KOC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.O. 3,831'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	219'	Cmtd. w/160 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.  
Push bridge plug to 1,510', pump 25 sax cement down drill pipe. Push bridge plug to 745', Pump 100 sax cement down drill pipe. Push bridge plug to 270', pump 40 sax cement down drill pipe. Push wiper plug to 40', dump 10 sax cement on plug to cellar. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole.

Name of Plugging Contractor Shields Drilling Co.

License No. RECEIVED

Address Shields Bldg., Russell, Kansas 67665

MAY - 6 2005

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R.P. Nixon Operations, Inc.

KOC WICHITA

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec.-Treas.

Contractor

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack P. Beeman

(Address) Shields Bldg., Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 3rd day of May, 2005

My Commission Expires:

Notary Public  
State of Kansas  
My Appt. Exp. 5-26-07

Form CP




# Shields

Russell, Kansas

## WELL LOG

Operator: R.P. Nixon Operations, Inc.  
 Well: Anna Seibel #1  
 Commenced: April 14, 2005  
 Completed: April 22, 2005  
 Contractor: Shields Drilling Co.

Well Description: 330' FNL, 330' FWL  
 NW/4 Sec. 16-14S-20W  
 Ellis Co., KS



### CASING RECORD

Size	Run	Pulled
8 5/8"	219'	Cmtd. w/160 sax

Elevation: 2,194' KB

Treatment:

Production: D & A

Tops:

..... Figures Indicate Bottom of Formations .....

Surface clay, sand, shale	133'
Shale	625'
Shale & sand	970'
Sand	1,200'
Shale & redbed	1,275'
Shale & sand	1,494'
Anhydrite	1,529'
Shale & sand	1,642'
Shale	3,070'
Shale & lime	3,510'
Lime	3,777'
Reagan Sand	3,831' RTD

RECEIVED  
 MAY - 6 2005  
 KCC WICHITA

Notes