

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-01790-00-00  
Spot: S2SWSE Sec/Twnshp/Rge: 5-12S-15W  
330 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: SUTTON A Well #: 2  
County: RUSSELL Total Vertical Depth: 3255 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 8100 E. 22ND N. BLDG. 300  
WICHITA, KS 67226

PROD Size: 5.5 feet: 3254 w/150 sxs cmt  
SURF Size: 8.625 feet: 868 w/475 sxs cmt

*\$105<sup>79</sup>*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/16/2005 9:00 AM  
Plug Co. License No.: 32452 Plug Co. Name: SMOKY HILLS WELL SERVICE  
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORPORATION Phone: (785) 483-9167

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 10% gel - 600# hulls.  
One joint tubing, two rods, pump barrel left in the hole.

Plugging Proposal Received By: JAY PFEIFER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/16/2005 12:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 1550' and 850'.  
TIH with tubing to 2800' - mixed and pumped 100 sxs cement with 500# hulls.  
Pulled up to 1400' - spotted 100 sxs cement.  
Pulled up to 800' - circulated cement with 75 sxs cement with 100# hulls.  
POOH. Swaged onto 5 1/2" and topped with 35 sxs cement.  
S.I.P. 500#.  
Hooked up to the annulus and pumped 40 sxs cement.  
S.I.P. 400#.

Perfs:

RECEIVED  
MAY 25 2005  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

*Jay Pfeifer*  
(TECHNICIAN)  
INVOICED

DATE 5-25-05

INV. NO. 2005061624


Form CP-2/3

MAY 20 2005

1-353

MA. NO. —  
 STATE Kans. COUNTY Russell SEC 5-12S-15W  
 OPER Louis M. Mai, Russell, Kansas LOC S/2 SW SE  
 WELL #2 FARM Sutton "A" — — — — —  
 FAIRPORT Fairport ELEV 1820 GR 1823 — — — — —  
 OPER Mast Drlg Tools GEOL. Francis Whisler — — — — —  
 TEST 3325' Oil Test. — — — — —

DATE 1/6/64 SPUD 1/6/64 COMP 2/4/64  
 TO 3255 Arb PSTD  
 PRODUCING FM FROM — TO PERI TREATMENT  
 Arb 3254-58 OH 250A  
 Co. Pump: 25 BOPD, NW, Grav. not available



8-5/8" @ 868 w/475 sx.  
 5 1/2" @ 3254 w/150 sx.

*Data Inc.*

KB Spl Tops & Datums:

Anh	865	+ 960	BKc	3207	-1382
Top	2672	- 847	Gor sd	3244	-1419
Hb	2892	-1067	Arb	3252	-1427
Tor	2912	-1087	RTD	3255	-1430
Kc	2946	-1121	DD TD	3258	-1433

DST #1 (Kc) 2914-63, Op 1 hr., WB/20", R 130' M, ISIP 380#/20"  
 IFP 0#, FFP 0#, FSIP 160#/20"  
 DST #2 (Kc) 2956-80, failed  
 RTD 3255 (Arb) No Log, 5 1/2" @ 3254 w/150 sx., CO & DD 3258 TD(Arb)  
 GSO, Nat, 250A, \$ 1d, \$ 1 1/2 BOPD, NW/8 hrs, POP, Co. P 25 BOPD,  
 NW, Arb 3254-58

COMPLETE (1/28/64)

1-353