

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-21764-00-00  
Spot: SENENE Sec/Twnshp/Rge: 18-9S-23W  
4290 feet from S Section Line, 330 feet from E Section Line  
Lease Name: KLENK Well #: 8  
County: GRAHAM Total Vertical Depth: 3904 feet

Operator License No.: 5135  
Op Name: FARMER, JOHN O., INC.  
Address: PO BOX 352 370 W WICHITA AVE  
RUSSELL, KS 67665

PROD Size: 4.5 feet: 3955 150 SX CMT  
SURF Size: 8.625 feet: 247 160 SX CMT

*\$126<sup>88</sup>*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/20/2005 12:00 PM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: DUANE EICHMAN Company: FARMER, JOHN O., INC. Phone: (785) 483-8355

Proposed Plugging Method: Ordered out 225 sxs 60/40 pozmix - 10% gel - 600# hulls - 13 sxs gel.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/20/2005 2:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Swaged onto 4 1/2" - mixed and pumped 25 sxs cement with 400# hulls, followed with 13 sxs gel spacer.  
Topped with 65 sxs cement and 100# hulls.  
Max. P.S.I. 1300#. S.I.P. 1000#.  
Hooked up to the annulus and pumped 50 sxs cement with 100# hulls.  
S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
3876	3881		

RECEIVED  
MAY 25 2005  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Jay Pfeifer (TECHNICIAN)

INVOICED

DATE 5-25-05

INV. NO. 2005061621

MAY 23 2005

JOHN O. FARMER, INC.  
P.O. BOX 352

#8 KLENK

18-9-23W  
SE NE NE


RUSSELL, KS 67665

CONTR COMPANY TOOLS

CTY GRAHAM

GEOLOGICAL

FIELD ERNST NW



ELV 2398 KB SPD 3/4/83 CARD ISSUED 6/2/83 IP P 32 BOPD  
LANS 3876-3881

API 15-065-21,764

LOG	Tops	Depth	Datum
ANH	.....	2040 +	358
HEEB	.....	3682-1284	
TOR	.....	3708-1310	
LANS	.....	3725-1327	
RTD	.....	3960-1562	

8 5/8 " 247/160SX; 4 1/2 " 3955/150SX  
DST (1) 3860-85 (LANS) / 45-45-45-45, 720' GIP, REC 120' O &  
GCM, SIP 183-193#, FP 51-61 / 71-71#  
DST (2) 3900-3925 (LANS) / 30-45-10-0, REC 5'M, ISIP 71#, FP  
51-51#  
MICT - CO, PF (LANS) 3876-81, W / 4 SPF. AC 2000G, SWB LD,  
R&T, POP, P 32 BOPD, 5.1.83

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS