

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-20890-00-02
Spot: SESENW Sec/Twnshp/Rge: 18-9S-23W
2310 feet from N Section Line, 2310 feet from W Section Line
Lease Name: ALBERTSON Well #: 1
County: GRAHAM Total Vertical Depth: 3965 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: PO BOX 352 370 W WICHITA AVE
RUSSELL, KS 67665

PROD Size: 4.5 feet: 3964 150 SX CMT
SURF Size: 8.625 feet: 201 150 SX CMT

\$128⁸⁶

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/20/2005 2:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DUANE EICHMAN Company: FARMER, JOHN O., INC. Phone: (785) 483-8355

Proposed Plugging Method: Ordered out 225 sxs 60/40 pozmix - 10% gel - 600# hulls - 13 sxs gel.
Perf at 2030' and circulate cement with 450 sxs.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/20/2005 4:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Swaged onto 4 1/2" - mixed and pumped 25 sxs cement with 400# hulls, followed with 13 sxs gel spacer.
Topped with 95 sxs cement and 100# hulls.
Max. P.S.I. 600#.
Annulus full of cement.

Perfs:

Top	Bot	Thru	Comments
3908	3913		
3871	3875		

RECEIVED
MAY 25 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

HD

Signed Jay Pfeifer (TECHNICIAN)

INVOICED

DATE 5-25-05

INV. NO. 200506621

MAY 23 2005

JOHN O FARMER
RUSSELL KS 67665

18-09S-23W
SE SE NW

1 ALBERTSON OWWO

site: 5 S & 2 E OF PENOKEE KS city: GRAHAM API: 15-065-20890
contr: POE WELL SVC / WESTERN WELL SVC field: ERNST NW (POOL OPENER)
prod: NONE
date 09/14/98 spd date 06/18/97 drig comp 06/18/97 card issued 09/14/98 last revised 09/14/98

ELV: 2381 KB, 2376 GL LOG
tops.....depth/datum
* ANH.....2030 +351
* B/ANH.....2064 +317
HEEB.....3678 -1297
TOR.....3703 -1322
LANS.....3719 -1338
BKC.....3946 -1565
RTD OLD.....3965 -1584
LTD OLD.....3965 -1584
* SAMPLE TOP

IP status:
INJ, LKC 3871-3913 OA, 07/18/97
NOTE: CORRECTION 9/14/98 - CORR CSG
OLD INFO: OPERATOR WAS JOHN O FARMER, 1
ALBERTSON, SPD 12/16/76, 12/23/76 8-5/8" 201 / 150
SX, 4-1/2" 3964 / 175 SX, OIL, P 100 BO & 2 BWPD, LKC
3871-3875, 12/30/76 (CARD ISSUED 01/27/77)
CONTR: JOHN O FARMER
NO CORES
DST (1) 3855-3875 (LKC), / 30-30-60-60, 1725' GIP, REC
240' OIL, 305' MDY OIL (85% OIL, GR 38) ISIP 1320#
FSIP 1320# IFP 64# -107# FFP 107# -226#

COPYRIGHT 1998
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)