

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-067-20401-00-00
Spot: SESESENW Sec/Twnshp/Rge: 31-28S-35W
2490 feet from N Section Line, 2340 feet from W Section Line
Lease Name: REED D Well #: 2
County: GRANT Total Vertical Depth: 3090 feet

Operator License No.: 5447
Op Name: OXY USA, INC.
Address: 5 E. GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

CIBP Size: feet: 2836 WITH 2 SX CMT
PROD Size: 4.5 feet: 3089 WITH 225 SX CMT \$100⁴³
SURF Size: 8.625 feet: 751 WITH 375 SX CMT

Well Type: GAS UIC Docket No: Date/Time to Plug: 05/16/2005 9:30 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: JOHN Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 2836' WITH 2 SX CMT. PLUG AT 1900' WITH 15 SX CMT. PLUG AT 780' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/16/2005 4:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

SET CIBP @ 2836' WITH 2 SX CMT ON TOP. CHECK WITH WIRELINE. TOP OF FLUID @ 2750'. PUMP 13 BBL MUD TO 1900'. 1ST PLUG PUMP 15 SX CMT AT 1900'. DISPLACE WITH MUD. 2ND PLUG PULL OUT OF HOLE TO 770'. LOAD HOLE WITH MUD & PUMP 50 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. PUMP 10 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2944	2962		
2912	2924		
2899	2905		
2892	2896		
2886	2889		
2007			to TOC

RECEIVED
MAY 27 2005
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1020' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

MAY 18 2005

MP

Signed

Jim Holland PART II
(TECHNICIAN)

INVOICED

DATE 5-27-05

INV. NO. 2005061633

Form CP 43