

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-20578-00-00
Spot: SESWNE Sec/Twnshp/Rge: 3-16S-27W
2310 feet from N Section Line, 1650 feet from E Section Line
Lease Name: MENDENHALL Well #: 1
County: LANE Total Vertical Depth: 4525 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH STREET
NEWTON, KS 67114

PROD Size: 4.5 feet: 4525 WITH 250 SX CMT
SURF Size: 8.625 feet: 335

147⁰⁶

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/10/2005 9:10 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: WAYNE Company: SWIFT SERVICES Phone: _____

Proposed Plugging Method: RUN TUBING TO 4000' & PUMP 25 SX CMT. PUMP 40 SX CMT AT 1600' & PRESSURE CHECK. PERFORATE AT 1350'. PLUG AT 690' WITH 40 SX CMT. PLUG AT 340' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/10/2005 3:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TUBING TO 4000' & FOUND SOLID BRIDGE, PUMPED 25 SX COMMON CMT. PUMPED 40 SX COMMON CMT WITH 3% CC AT 1600'. WAITED 1 1/2 HOURS AND PRESSURED TO 500#. PERFORATED AT 1350' & PUMPED 80 SX CMT. PULLED CASING TO 650' & PUMPED 40 SX CMT. PULLED CASING TO 340' & PUMPED 50 SX CMT. PULLED REST OF CASING & TOPPED OFF WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4336	4357		

RECEIVED
MAY 27 2005
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL & COMMON CMT W/3% XX BY SWIFT SERVICES. RECOVERED 690' OF 4 1/2" CASING.

Plugged through: TBG

District: 01

MAY 16 2005

MA

Signed

Michael J. Maier
(TECHNICIAN)

INVOICED

DATE 5-27-05

INV. NO. 2005061634

Form SP-28