

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-20695-00-00
Spot: NWNENE Sec/Twnshp/Rge: 3-16S-27W
330 feet from N Section Line, 990 feet from E Section Line
Lease Name: MENDENHALL Well #: 3
County: LANE Total Vertical Depth: 4520 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH STREET
NEWTON, KS 67114

PROD Size: 5.5 feet: 4492 WITH 250 SX CMT
SURF Size: 8.625 feet: 324

#146⁹⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/12/2005 9:40 AM

Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC

Proposal Rcvd. from: WAYNE Company: SWIFT SERVICES Phone: _____

Proposed Plugging Method: SAND TO 4200' & 4 SX CMT. PERFORATE AT 1250'. PUMP 80 SX CMT. PUMP 50 SX CMT FREE POINT. 50 SX CMT AT 360'. 10 SX CMT AT 40'.

Plugging Proposal Received By: STEVE DURRANT

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 05/12/2005 2:30 PM

KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SANDED TO 4200' & 4 SX CMT. RUN TUBING TO 2030' & PUMP 25 SX COMMON CMT WITH 3% CC. PULLED TUBING AND WAITED 1 HOUR. PRESSURED CASING TO 500#. PERFORATED AT 1250'. PUMP 80 SX CMT. DISPLACED CMT TO 1000'. PULLED CASING TO 650' & PUMPED 40 SX CMT. PULLED CASING TO 330' & PUMPED 50 SX CMT. PULLED CASING & TOPPED OFF WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4425	4441		

RECEIVED
MAY 27 2005
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL & COMMON CMT W/3% CC BY SWIFT SERVICES. RECOVERED 690' OF 5 1/2" CASING.

Plugged through: TBG

District: 01

MAY 16 2005

AP

Signed

Michael J. Maier

(TECHNICIAN)

INVOICED

DATE 5-27-05

INV. NO. 20050616 34

[Signature]
Form CR-273