

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-067-20514-00-00
Spot: SESESENW Sec/Twnshp/Rge: 11-29S-35W
2340 feet from N Section Line, 2540 feet from W Section Line
Lease Name: DIEHL A Well #: 2
County: GRANT Total Vertical Depth: 3089 feet

Operator License No.: 5447 CIBP Size: feet: 2826 WITH 2 SX CMT
Op Name: OXY USA, INC. PROD Size: 4.5 feet: 3088 WITH 225 SX CMT
Address: 5 E. GREENWAY PLZ PO BOX 27570 SURF Size: 8.625 feet: 734 WITH 400 SX CMT **\$100³⁹**
HOUSTON, TX 77227

Well Type: GAS UIC Docket No: Date/Time to Plug: 05/11/2005 1:30 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: JOHN Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: CIBP OVER PERFS. 15 SX CMT AT 1800'. 50 SX CMT AT 750'. 10 SX CMT AT 40'.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/12/2005 11:00 AM KCC Agent: JIM HOLLAND

Actual Plugging Report:

SET CIBP @ 2826' WITH 2 SX CMT ON TOP. CHECK WITH WIRELINE & TAG FLUID. 1ST PLUG PUMP MUD SPACER TO 1800' & PUMP 15 SX CMT AT 1800'. DISPLACE WITH MUD. 2ND PLUG CIRCULATE HOLE WITH MUD. PUMP 50 SX CMT AT 720'. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40' & PUMP 10 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2931	2942		
2901	2926		
2876	2885		
1860			to TOC

RECEIVED
MAY 27 2005
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 720' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

MAY 18 2005

MP

Signed Jim Holland PART II
(TECHNICIAN)

INVOICED
DATE 5-27-05
INV. NO. 2005061633

Form CP-2/3

[Handwritten Signature]