

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-20116-00-00  
Spot: SESESENW Sec/Twnshp/Rge: 7-29S-34W  
2340 feet from N Section Line, 2540 feet from W Section Line  
Lease Name: HOWELL A Well #: 2  
County: HASKELL Total Vertical Depth: 3180 feet

Operator License No.: 5447 CIBP Size: feet: 2808 WITH 2 SX CMT  
Op Name: OXY USA, INC. PROD Size: 4.5 feet: 3179 WITH 275 SX CMT  
Address: 5 E. GREENWAY PLZ PO BOX 27570 SURF Size: 8.625 feet: 727 WITH 400 SX CMT  
HOUSTON, TX 77227

#103<sup>35</sup>

Well Type: GAS UIC Docket No: Date/Time to Plug: 05/12/2005 3:00 PM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 2808' WITH 2 SX CMT. PLUG AT 1800' WITH 15 SX CMT. PLUG AT 750' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/13/2005 1:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

SET CIBP @ 2808' WITH 2 SX CMT ON TOP. CHECK WITH WIRELINE. TAG TOP OF FLUID. 1ST PLUG PUMP MUD SPACER TO 1800' & PUMP 15 SX CMT AT 1800'. 2ND PLUG PULL OUT OF HOLE TO 750'. CIRCULATE HOLE WITH MUD & PUMP 50 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2857	2930		
2180			

RECEIVED  
MAY 27 2005  
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1036' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

MAY 18 2005

*MP*

Signed

Jim Holland PIRTT  
(TECHNICIAN)

INVOICED

DATE 5-27-05

INV. NO. 2005061633

Form CP-235