

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-10225-00-01
Spot: SE Sec/Twnshp/Rge: 4-35S-42W
1320 feet from S Section Line, 1320 feet from E Section Line
Lease Name: HAYWARD NATIONAL UNIT Well #: 1
County: MORTON Total Vertical Depth: 4815 feet

Operator License No.: 33002 CIBP Size: feet: 2737
Op Name: WESTPORT OIL AND GAS COMPANY L PROD Size: 5.5 feet: 3035 WITH 350 SX CMT
Address: 5735 PINELAND, SUITE 300 RBP Size: feet: 2927
DALLAS, TX 75231 SURF Size: 8.625 feet: 1388 WITH 750 SX CMT

\$ 156.49

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/06/2005 9:30 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Revd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 400# HULLS & 25 SX CMT. PLUG AT 1400' WITH 50 SX CMT. PLUG AT 600' WITH 30 SX CMT. PLUG AT 40-0' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/06/2005 4:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PUMP 400# HULLS WITH 25 SX CMT. DISPLACE WITH MUD. PRESSURE TO 500 PSIG & SHUT IN. 1ST PLUG PULL OUT OF HOLE TO 1400'. CIRCULATE HOLE & PUMP 50 SX CMT. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 600'. LOAD HOLE & PUMP 30 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 2934 | 2970 | | |
| 2912 | 2918 | | |
| 2898 | 2900 | | |
| 2811 | 2813 | | |
| 2772 | 2774 | | |
| 2719 | 2728 | | |
| 2708 | 2711 | | |
| 2681 | 2685 | | |
| 2484 | 2489 | | |

RECEIVED
MAY 27 2005
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1529' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

MAY 12 2005

MD

Signed

Michael J. Ware

(TECHNICIAN)

INVOICED

DATE 5.27.05
INV. NO. 2005061639

Form CP-2/3