

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-21655-00-00  
Spot: NWNE Sec/Twnshp/Rge: 8-18S-7W  
4950 feet from S Section Line, 940 feet from E Section Line  
Lease Name: YOST-TIMMONS Well #: 4  
County: RICE Total Vertical Depth: 3242 feet

Operator License No.: 8917  
Op Name: GUSTUS, DEAN DBA JD PRODUCTION  
Address: 701 MAIN  
GENESEO, KS 67444

PROD Size: 5.5 feet: 3239 100 SX CMT  
SURF Size: 8.625 feet: 395 300 SX CMT

*10537*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/05/2005 2:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (316) 938-2537

Proposed Plugging Method: Sand to 3150' and cap with 5 sacks of cement. Pull pipe to 1050' and pump 35 sacks of cement. Pull pipe to 700' and pump 35 sacks of cement. Pull pipe to 450' and circulate to surface from there.

Plugging Proposal Received By: GREG EVES WitnessType: PARTIAL  
Date/Time Plugging Completed: 05/05/2005 4:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

Sanded to 3150' and capped with 5 sacks of cement. Pulled 30 joints after cutting at 2315' and pumped 35 sacks of cement at 1050'. Pulled 8 joints and pumped 35 sacks of cement at 700'. Pulled 5 joints, pumped 145 sacks of cement from 450', and circulated to surface.

Allied Cement #20665  
215 sacks total  
60/40 posmix with 4% gel

Perfs:

Top	Bot	Thru	Comments
3234			
<b>RECEIVED KCC DISTRICT #2 MAY 10 2005 WICHITA, KS</b>			
<b>RECEIVED KANSAS CORPORATION COMMISSION MAY 27 2005</b>			
CONSERVATION DIVISION WICHITA KS			

Remarks:

Plugged through: CSG

District: 02

Signed Greg Eves  
(TECHNICIAN)

**INVOICED**

DATE 5-27-05

INV. NO. 2005061631