

RECEIVED

APR 16 2003

KCC WICHITA

15-163-30213-00-01

8/30/66

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM

(PLEASE TYPE FORM and File ONE Copy)

API # _____ (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR JOHNSON OIL CO KCC LICENSE # 3077
(owner/company name) (operator's)

ADDRESS 258 east highway 36 CITY phillipsburg kansas 67661

STATE ks ZIP CODE 67661 CONTACT PHONE # (785) 543 6171

LEASE holsman WELL# 2 SEC. 15 T. 7s R. 19w (East/West)

w/2 sw se- _____ SPOT LOCATION/QQQQ COUNTY rooks

660s FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

2310 east FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL _____ D&A _____ SWD/ENHR WELL _____ DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 7 inch SET AT 1202 CEMENTED WITH 325 circulated SACKS

PRODUCTION CASING SIZE 4 1/2 SET AT 3395 CEMENTED WITH 175 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: none

ELEVATION 1921.5 T.D. 3391 PBTD 3371 ANHYDRITE DEPTH 1375
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD _____ POOR _____ CASING LEAK xxx JUNK IN HOLE packer

PROPOSED METHOD OF PLUGGING RUN TUBING to 2900 pump 40 sacks common

then pump cement to 1150 pull pipe run in perferater shoot at 1151

run pipe back to 1150 pump cement until circulates pull pipe then top off hole
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

KEVIN JOHNSON PHONE# () 785 543 6171

ADDRESS 258 east highway 36 City/State phillipsburg kansas 67661

PLUGGING CONTRACTOR allied cementing KCC LICENSE # n/a
(company name) (contractor's)

ADDRESS russell kansas PHONE # () _____

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 4-4-03 plugged

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: April 14/2003 AUTHORIZED OPERATOR/AGENT: [Signature]
(signature)