

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 130 S. Market, Room 2078
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 8-30-66 15-163-30213-00-01

LEASE NAME holzman 2

WELL NUMBER 2

660s Ft. from S Section Line

2310 ^{EAST} Ft. from E Section Line

SEC. 15 TWP. 7s RGE. 19w (E) or (W)

COUNTY ROOKS

Date Well Completed 8-30-66

Plugging Commenced 4-4-2003

Plugging Completed 4-4-2003

RECEIVED
 4/16/03
 APR 16 2003

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

KCC WICHITA JOHNSON OIL
 LEASE OPERATOR _____

ADDRESS 258 east highway 36

PHONE(S) 785 543 6171 OPERATORS LICENSE NO. 3077

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-4-2003 (date)

by BRUCE BASEY DISTRICT 4 (KCC District Agent's Name).

Is ACO-1 filed? yes if not, is well log attached? _____

Producing Formation KANSAS CITY Depth to Top 3119 Bottom 3300 T.D. 3391

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
7 inch	casing surface	1202	to surface	325	sacks	circulated to surface
4 1/2 production casing	cemented with	175	sacks	not at	3305	all in hole

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Tubing and packer was run to 2900 packer stuck. we then pumped 40 sacks common cement flushed tubing. then we got off packer pulled 1 joint of tubing then brought cement to 1150. 70 sacks. Pulled tubing out of hole then perforated 4 1/2 at 1151 ran pipe back to 1150 pumped 230 sacks. cement circulated

then we pulled pipe, topped of hole. job done. 2 days later checked cement level to be 10ft from surface.

Name of Plugging Contractor allied cementing License No. n/a

Address russel kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: KEVIN JOHNSON

STATE OF kansas COUNTY OF rooks, ss.

Kevin Johnson oil (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Kevin Johnson


(Address) 258 EAST HIGHWAY 36

SUBSCRIBED AND SWORN TO before me this 14th day of April, 192003

Waneta Fae Gower
 Notary Public

My Commission Expires: 12-05-2003

Form CP-4
 Revised 05-88



ALLIED CEMENTING CO., INC. 13408

Federal Tax I.D. # XXXXXXXXXX

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Russell

DATE <u>4-4-03</u>	SEC.	TWP.	RANGE	CALLED OUT <u>3:30pm</u>	ON LOCATION <u>5:30pm</u>	JOB START	JOB FINISH <u>8:30pm</u>
LEASE <u>Holzman</u>		WELL # <u>2</u>		LOCATION <u>Webster 2N 2W</u>		COUNTY <u>Rooks</u>	STATE <u>Ka</u>

OLD OR NEW (Circle one)

CONTRACTOR CoTools

TYPE OF JOB Plug

HOLE SIZE _____ T.D. _____

CASING SIZE _____ DEPTH _____

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT _____

OWNER _____

CEMENT

AMOUNT ORDERED
400 new 60/40-10
~~300 new 60/40-10~~ Used 300 new 60/40-10

COMMON	<u>100</u>	@	<u>7.25</u>	<u>1287.00</u>
POZMIX	<u>120</u>	@	<u>3.80</u>	<u>456.00</u>
GEL	<u>21</u>	@	<u>10.00</u>	<u>210.00</u>
CHLORIDE		@		
		@		
		@		
		@		
		@		
		@		
HANDLING	<u>400</u>	@	<u>1.15</u>	<u>460.00</u>
MILEAGE	<u>54/51</u>	/Mile		<u>800.00</u>

TOTAL 3213.00

EQUIPMENT

PUMP TRUCK CEMENTER Bill

177 HELPER PAUL

BULK TRUCK

362 DRIVER Refus

BULK TRUCK

282 DRIVER Shane

REMARKS:

40 cpm furnished by customer
Tubing @ 2900 Spot 40 cpm
pull 1st. Spot 70 cpm 60/40 10% gel
pull to 1150' perforate,
pump 230 lb 60/40-10 circ. to surface
pull tubing

SERVICE

DEPTH OF JOB _____

PUMP TRUCK CHARGE _____ 175.00

EXTRA FOOTAGE _____ @ _____

MILEAGE 40 @ 3.50 140.00

PLUG _____ @ _____

_____ @ _____

_____ @ _____

RECEIVED

APR 16 2003

TOTAL 615.00

CHARGE TO: Johnson Oil

STREET _____

CITY _____ STATE _____ ZIP _____

KCC WICHITA

FLOAT EQUIPMENT

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE [Signature]

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

PRINTED NAME _____