

15163-30120-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Rooks SEC. 15 TWP. 7 RGE. 19 EW  
Location as in quarters or footage from lines:  
330' from south line. 990' from west line


Lease Owner Thomason Oil Company  
Lease Name Holsman Well No. 1  
Office Address 2700 Oak St., Suite A Hays, KS 67601  
Character of Well (Completed as Oil, ~~Gas or Dry Hole~~): Oil  
Date Well Completed September 3, 1965  
Application for plugging filed April 26, 1983  
Plugging commenced August 16, 1983 @ 10:00 AM  
Plugging completed August 16, 1983 @ 1:16 PM  
Reason for abandonment of well or producing formation Not profitable for production

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dennis Hammell

Producing formation Top., KC, Arb Depth to top 3072' bottom 3420' T.D. 3429'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
<u>Topeka</u>	<u>Lime</u>	<u>3072</u>	<u>26</u>	<u>8 5/8"</u>	<u>278'</u>	<u>None</u>
<u>KC/C Zone</u>	<u>Lime</u>	<u>3180</u>	<u>24</u>	<u>5 1/2"</u>	<u>3407'</u>	<u>None</u>
<u>KC/J Zone</u>	<u>Lime</u>	<u>3312</u>	<u>18</u>			
<u>Arbuckle</u>	<u>Dolomite</u>	<u>3420</u>	<u>22</u>			

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_  
feet to \_\_\_\_\_ feet for each plug set. Allied Cementing pumped 50 sxs of 50/50 Pos 6% Gel;  
18 sxs Gel 100 sxs of 50/50 Pos 6% Gel down 5 1/2" casing. Then pumped 150 sxs of 50/50  
Pos 6% gel down 8 5/8" surface pipe. Allied Cementing did all the work.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor \_\_\_\_\_

AUG 19 1983  
8/18/83  
WICHITA, KANSAS

STATE OF KANSAS COUNTY OF ELLIS, ss.

Steven Thomason (employee of owner) ~~or (owner or operator)~~ of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) Steven Thomason  
2700 Oak St., Suite A  
(Address) Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 17th day of August, 19 83

NOTARY PUBLIC - State of Kansas  
Roxie VonLintel  
My Appt. Exp. 5-21-85

Roxie VonLintel  
Notary Public.

My Commission expires: