


15-163-00401-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Rooks _____ County. Sec. 16 Twp. 7 Rge. 19 (E) W (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW SE SE
Lease Owner DEEP ROCK OIL CORPORATION
Lease Name Griebel Well No. 1
Office Address Box #1051, Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 2 19 51
Application for plugging filed September 7 19 51
Application for plugging approved September 14 19 51
Plugging commenced September 24 19 51
Plugging completed October 10 19 51
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation Kansas City Depth to top 3152' Bottom 3358' Total Depth of Well 3453' P.E. 3371'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled Out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8 | 224' | None |
| | | | | 5 1/2" | 3416' | 1303' |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with mud from 3453' and set Lane-Well plug at 3371'. Put in sand from 3371' to 3290'. Put in 4 sacks cement at 3290' and filled with heavy mud to 224'. Set rock bridge at 224' and put in 40 sacks cement. Put in heavy mud to 35' and set rock bridge. Ran 10 sacks cement, filled to top of hole and into cellar.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Deep Rock Oil Corporation
Address Box #1146, Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Reno, ss.
Jack Smith

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack Smith

Box #1146, Hutchinson, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of October, 1951

RECEIVED
STATE CORPORATION COMMISSION
Notary Public.

My commission expires August 2, 1952

23-3273-s 4-50-10M

PLUGGING
FILE SEC 16 T 7 R 19 W
BOOK PAGE 109 LINE 15

OCT 18 1951
OCT 18 1951