

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: John O. Farmer, Inc.

Address: P.O. Box 352, Russell, KS 67665

Phone: (785) 483-3144 Operator License #: 5135

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)

by: District #4 (KCC District Agent's Name)

Is ACO-1 filed? Yes No if not, is well log attached? Yes No

Producing Formation(s): List All (if needed attach another sheet)

Lansing Depth to Top: 3725' Bottom: 3960' T.D. 3960'

API Number: 15 - 065-21,764 - 00 - 00

Lease Name: Klenk

Well Number: #8

Spot Location (QQQQ): _____ - SE - NE - NE
990 Feet from North / South Section Line

330 Feet from East / West Section Line

Sec. 18 Twp. 9 S. R. 23 East West

County: Graham

Date Well Completed: 4/83

Plugging Commenced: 12:30 P.M., 5-20-05

Plugging Completed: 1:30 P.M., 5-20-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Lansing "I"	oil & water	3876'	3881'	8-5/8"	247'	-0-
				4-1/2"	3955'	-0-

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

The casing was perforated prior to plugging: 2 holes @ 1300' & 2 holes @ 2000'. Mixed 25 sks. cement & 13 sks. gel w/400# hulls - followed by 65 sks. cement & 100# hulls. Maximum pressure, 1000 PSIG. Shut in @ 800 PSIG. Hooked on backside & mixed 50 sks. cement w/100# hulls - maximum pressure, 400 PSIG. Shut in @ 100 PSIG.

Name of Plugging Contractor: Allied Cementing Company, Inc. License #: 99996

Address: P.O. Box 31, Russell, KS 67665

Name of Party Responsible for Plugging Fees: John O. Farmer, Inc.

State of Kansas County, Russell, ss.

John O. Farmer IV (Employee of Operator) or (Operator) on above-described well, being first duly


sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) John O. Farmer IV

(Address) P.O. Box 352, Russell, KS 67665

SUBSCRIBED and SWORN TO before me this 27th day of May, 20 05

Margaret A. Schulte My Commission Expires: _____
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
MAY 31 2005
KCC WICHITA

Bu

