

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-11061-00-00  
Spot: NWNWNE Sec/Twnshp/Rge: 31-25S-13W  
330 feet from N Section Line, 2310 feet from E Section Line  
Lease Name: CAMP Well #: 2  
County: STAFFORD Total Vertical Depth: 4274 feet

Operator License No.: 3911  
Op Name: RAMA OPERATING CO., INC.  
Address: 101 S. MAIN  
STAFFORD, KS 67578

CIBP Size: feet: 3650 WITH 2 SX CMT  
PROD Size: 7 feet: 4271 WITH 200 SX CMT  
SURF Size: 10.75 feet: 1298 WITH 600 SX CMT

#138<sup>91</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/25/2005 9:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: CIBP @ 3650' & 2 SX CMT. PLUG AT 1330' WITH 20 SX GEL - 75 SX CMT - 200# HULLS. PLUG AT 800' WITH 40 SX CMT - 100# HULLS. PLUG AT 400' WITH 45 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/25/2005 2:10 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

ANHYDRITE TOP: 800'. SET CIBP @ 3650' WITH 2 SX CMT ON TOP OF PLUG. 1ST PLUG AT 1330' WITH 20 SX GEL - 75 SX CMT - 200# HULLS. 2ND PLUG AT 800' WITH 40 SX CMT - 100# HULLS. 3RD PLUG AT 400' WITH 45 SX CMT. 4TH PLUG AT 40' WITH 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4190	4202		
3954	3960		
3933	3937		
3928	3932		
3888	3896		
3860	3863		
3749	3753		
3702	3710		

RECEIVED  
MAY - 9 2005  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2100' OF 7".

Plugged through: CSG

District: 01



Signed Richard M. Lacey  
(TECHNICIAN)

INVOICED  
DATE 5-10-05  
INV. NO. 2005061544

Form CP-28