

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-30213-00-01
Spot: W2SWSE Sec/Twnshp/Rge: 15-7S-19W
660 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: HOLSMAN Well Number: 2-A
County: ROOKS Total Vertical Depth: 3395 feet

Operator License No.: 3077
Op Name: JOHNSON OIL
Address: 258 HWY 36
PHILLIPSBURG, KS 67661

Production Casing Size: 4.5 feet: 3391 w/75 sxs cmt
Surface Casing Size: 7 feet: 1202 w/325 sxs cmt
w/325 sxs cmt

\$110.34

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/04/2003 12:00 PM

Plug Co. License No.: 3077 Plug Co. Name: JOHNSON OIL

Proposal Rcvd. from: KEVIN JOHNSON Company: JOHNSON OIL Phone: (785) 543-6171

Proposed Plugging Method: Junk in hole - packer stuck at 2900'. Perfs open at 3200' to 3318'.
Pump 40 sxs common through tubing and packer at 2900'.
Shoot tubing above packer - pull one joint and pump 80 sxs 60/40 pozmix - 10% gel.
Pull tubing to 1150' and displace cement with water.
Use slim hole shots to perforate 7" casing.
Pump 140 sxs 60/40 pozmix - 10% gel.
Pull tubing and top off with 10 sxs 60/40 pozmix - 10% gel.

Plugging Proposal Received By: BRUCE BASYE

Witness Type: Plugging Operations Were Not Witnessed

Date/Time Plugging Completed: 04/04/2003 4:00 PM

KCC Agent: BRUCE BASYE

Actual Plugging Report:

Pumped 40 sxs common through stuck packer at 2900'.
Backed off tubing above packer - pulled one joint.
Pumped 70 sxs 60/40 pozmix - 10% gel. Pulled tubing.
Went in hole with gun and shot two holes at 1150'. Ran tubing to 1150'.
Pumped 230 sxs 60/40 pozmix - 10% gel and brought cement to surface up 4 1/2" casing and 4 1/2" x 7" annulus.
Pulled tubing and topped off with 5 sxs 60/40 pozmix - 10% gel.
Hole stayed full.

RECEIVED
APR 18 2003
KCC WICHITA
4/18/07

Remarks: ALLIED CEMENTING COMPANY

Plugged through: TBG

District: 04

Signed

Bruce D. Basye

(TECHNICIAN)

INVOICED

DATE 4-21-03

INV. NO. 2003061434

Form CP-2/3

APR 07 2003

AYLWARD DRLG. CO.
WICHITA, KS.

CORRECTED CARD
#2-A HOLSMAN

15-7-19W
APPX W/2 SW SE

CONTR ABERCROMBIE DRLG., INC. CTY ROOKS

GEOL _____ FIELD GROVER

E 1927 DF CM 8/20/66 CARD ISSUED 9/22/66 IP P 18 BOPD, NW
LANS 3274-78 &
3293-98

+	+	+
+	+	+
+	+	+

API

SMP	TOPS	DEPTH	DATUM
ANH		1432	+ 495
TOP		2877	- 950
HEEB		3078	-1151
TOR		3105	-1178
LANS		3119	-1192
BKC		3343	-1416
ARB		3387	-1460
TD		3395	-1468

7" 1202/325sx, 4" 3391/75sx
DST (1) 3265-3300/40", 10' OCM, SS
FREE OIL, SIP 307-255#/20", FP
36-51#
MICT - CO 3371, PF 20/3293-98 & 16/
3274-78, SWB 1GO + 2 GW/45", AC 1000,
REC LD, SWB 3 BO + 3 BW/1HR, SWB 10
BF, AC 3000, REC LD, SWB DWN, SET
TBG, POP, TWIN TO #2-LOST HOLE

CORRECTED CARD: 1/19/79

CORRECTED SPUD DATE, WELL NUMBER,
LOCATION

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

7