

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-031-19045-00-00
Spot: NENWSE Sec/Twnshp/Rge: 2-23S-16E
2410 feet from S Section Line, 1500 feet from E Section Line
Lease Name: MURRAY Well #: 5C
County: COFFEY Total Vertical Depth: 978 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: P.O. BOX 388
IOLA, KS 66749

PROD Size: 4.5 feet: 855
SURF Size: 8 feet: 20

35⁰⁰

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/17/2005 8:00 AM
Plug Co. License No.: 5150 Plug Co. Name: COLT ENERGY INC
Proposal Rcvd. from: DENNIS KERSHNER Company: COLT ENERGH. INC. Phone: (620) 365-3111

Proposed Plugging Method: THIS WELL CONSISTED OF 4.5" CASING TO 855' THAT HAD BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO PLACE AT LEAST A 50" CEMENT PLUG AT T.D., A 50' CEMENT PLUG AT 700', AND A CONTINUOUS CEMENT PLUG FROM 250' TO SURFACE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: NONE
Date/Time Plugging Completed: 04/04/2005 5:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

Perfs:

1" PIPE WAS RAN TO 975' AND THE BOTTOM PLUG WAS PUMPED. THE 1" WAS REMOVED. THE 4.5" CASING WAS SHOT OFF AT 702' AND 702' OF 4.5" CASING WAS PULLED FROM THE WELL. 2" TUBING WAS RAN TO 703' AND 25 SACKS OF CEMENT WAS PUMPED TO THAT DEPTH. THE 2" WAS PULLED TO 600' AND 60 SACKS OF CEMENT WERE PUMPED TO THAT DEPTH. THE 2" WAS PULLED TO 250'. CEMENT WAS PUMPED INTO THE 2" TUBING UNTIL CEMENT CIRCULATED FROM THE WELL AT SURFACE. THE 2" WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

RECEIVED
KCC DISTRICT #3

MAY 25 2005

CHANUTE, KS

CPT

RECEIVED
MAY 31 2005
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed

Clayton P. Titel

(TECHNICIAN)

INVOICED

DATE

6-1-05

WV. NO.

2005061641