

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-207-26878-00-00
Spot: NENWENW Sec/Twnshp/Rge: 10-24S-17E
260 feet from N Section Line, 1720 feet from W Section Line
Lease Name: WILLIE NORTH Well #: 06-04
County: WOODSON Total Vertical Depth: 1245 feet

Operator License No.: 30345
Op Name: PIQUA PETRO, INC.
Address: 1331 XYLAN ROAD
PIQUA, KS 66761

SURF Size: 7 feet: 20

\$40⁴⁶

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/17/2005 10:00 AM
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC
Proposal Rcvd. from: GREG LAIR Company: PIQUA PETRO, INC. Phone: (620) 433-0099

Proposed Plugging Method: THIS WELL CONSISTED OF AN UNCASSED BORE TO 1245'. THE PLUGGING PROPOSAL WAS TO PLACE AT LEAST A 50' CEMENT PLUG AT T.D., A 50' CEMENT PLUG AT 700', AND A CONTINUOUS CEMENT PLUG FROM 250' TO SURFACE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: NONE
Date/Time Plugging Completed: 01/17/2005 3:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

Perfs:

1" PIPE WAS RAN TO 1245'. 20 SACKS OF CEMENT WERE PUMPED THROUGH THE 1" PIPE TO 1245'. THE PIPE WAS PULLED TO 700'. 10 SACKS OF CEMENT WERE PUMPED TO THAT DEPTH. THE 1" PIPE WAS PULLED TO 600'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE WELL AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

RECEIVED
MAY 31 2005
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed Clayton P. Titel
(TECHNICIAN)

INVOICED

DATE 6-1-05

INV NO 2005061643