

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-00828-00-00
Spot: SESENW Sec/Twnshp/Rge: 32-26S-6E
2894 feet from S Section Line, 2947 feet from E Section Line
Lease Name: WEBBER Well #: 1
County: BUTLER Total Vertical Depth: 2771 feet

Operator License No.: 7228
Op Name: BRICKLEY, DONALD DBA D & J INVES
Address: 138 N. ALLEGHANY
EL DORADO, KS 67042

PROD Size: 5.188 feet: 2468

\$90⁰⁶

Well Type: OIL UIC Docket No: Date/Time to Plug: 04/27/2005 8:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: DON BRICKLEY Company: D & J INVESTMENTS Phone: (316) 321-0410

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DONALD HOBERECHT WitnessType: PARTIAL
Date/Time Plugging Completed: 05/10/2005 5:00 PM KCC Agent: DONALD HOBERECHT

Actual Plugging Report:

Sanded back 50' above perforations; open hole with 5 sacks of cement on top of sand. Shot casing at 300' and pulled to surface. Bailed fluid down to 250' and filled with 4-1/2 yds of slurry mix. Dug out cellar and ran 1" between 8-5/8" and 24" to 206'. Filled to surface with 250 sacks of 60/40 posmix with 4% gel.

Lewis and Clark slurry mix and cementing by United #6266

Perfs:

RECEIVED
KCC DISTRICT #2
MAY 31 2005
WICHITA, KS


RECEIVED
JUN - 1 2005
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

INVOICED

DATE

6-1-05

INV. NO.

2005061646